

Summary of Changes to Measurement & Payment and Master Bid List Documents

September 12, 2005

M&P and bid item changes:

Items added:

#	015710025	Check Dam (Fiber Roll)	Feet
---	-----------	------------------------	------

#	015710075	Drop-Inlet Barrier (Fiber Roll)	Feet
In place, along the centerline of fiber roll			

#	015710110	Pipe-Inlet Barrier (Stone)	Cubic yard
In place			

#	015710120	Sediment Trap	Cubic yard
Of material excavated			

#	015710130	Stabilized Construction Entrance	Square yard
In place			

#	015710140	Straw Bale Barrier	Feet
In place			

Items deleted:

015710010	Check Dam (straw or Hay Bale)	Feet
015710050	Drop-Inlet Barriers (Straw or Hay Bale)	Feet
015710080	Sediment Trap	Cubic Feet