

Research Division Annual Work Program State Fiscal Year 2006

Prepared For:

Utah Department of Transportation Research
and Development Division

Authored By:

Michelle A. Page, Program Manager
Ken Berg, Development Engineer

June 2005

UDOT RESEARCH & DEVELOPMENT REPORT ABSTRACT

1. Report No. UT-05.08		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle: Research Division Annual Work Program State Fiscal Year 2006		5. Report Date: June 2005			
		6. Performing Organization Code:			
7. Author(s): Michelle A. Page, P.E., Program Manager Ken Berg, P.E., Development Engineer Utah Department of Transportation, Research Division		8. Performing Organization Report No.			
9. Performing Organization Name and address: Utah Department of Transportation Research Division 4501 South 2700 West Taylorsville, Utah 84119		10. Work Unit No.			
		11. Contract No.			
12. Sponsoring Agency Name and Address: Utah Department of Transportation Research Division 4501 South 2700 West Taylorsville, Utah 84119		13. Type of Report and Period Covered			
		14. Sponsoring Agency Code			
15. Supplementary Notes:					
16. Abstract: The purpose of this publication is to provide a progress report and a working plan for the management of the research, development and implementation activities of the Utah Department of Transportation (UDOT) for the 2006 State Fiscal Year. All funding sources with their associated work plans are included.					
17. Key Words: FY06 Work Program			18. Distribution Statement Available: UDOT Research Division Box 148410 Salt Lake City, Utah 84114-8410 www.dot.utah.gov/res		
19. Security Classification (Of this report)	20. Security Classification (Of this report)	21. No. of Pages	22. Price		

DISCLAIMER

The contents of this report reflect the view of the authors, who are responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the Utah Department of Transportation (UDOT).

Utah Department of Transportation

Research Division Annual Work Program

State Fiscal Year 2006*

(July 1, 2005 to June 30, 2006)

Annual Status Report

TOOLS



FOR



BETTER TRANSPORTATION TOMORROW

June 2005

THIS PAGE LEFT BLANK INTENTIONALLY

Introduction

The purpose of this publication is to provide a progress report and a working plan for the management of the research, development and implementation activities of the Utah Department of Transportation (UDOT) for the 2006 state fiscal year. All funding sources with their associated work plans are included. A companion document entitled, *Manual for Management of UDOT's Research, Development and Technology Transfer Program*, dated December 1995, will aid in characterizing UDOT's research program. It also provides the management framework required under Chapter 23 of the Code of Federal Regulations (CFR), Part 420, Subpart B, for the State's administration of State Planning and Research (SPR) funds. This plan was approved by FHWA on January 10, 1996.

Historical Factors that Helped to Shape the Current Research Division Program

Research was one of the principal missions of the first national highway program in the United States and is the oldest continuous federal highway activity. The Federal Highway Act of 1921 authorized the first sustained fiscal support for highway research. Support for highway research was reaffirmed in the Federal-Aid Highway Act of 1962, which mandated funds for planning and research purposes only. Most recently, the Intermodal Surface Transportation Efficiency Act (ISTEA) of 1991 required that a minimum of 25% of the State Planning and Research (SPR) funds be expended on research, development and technology transfer activities.

During the late 1980's, the Department underwent significant downsizing, resulting in the loss of experienced personnel and trained research professionals. As a response, a greater percentage of research was performed by outside sources. It was felt that outside sources would bring greater expertise and efficiency for many subject areas. This continues to be the practice. A large percentage of the research projects are currently performed by either universities or consultants in the private sector. For these projects, the Research Division performs project management functions. It has been found, however, that some topics could not be efficiently or effectively addressed by outside sources because of their lack of institutional knowledge related to areas of specific transportation expertise. Therefore, a small percentage of research, as well as most development and technology transfer activities, continue to be performed in-house.

UDOT's research, development and technology transfer functions were separated from Materials and set up as a separate division in 1993. About this time, the process of facilitating an annual workshop in which UDOT stakeholders can brainstorm and prioritize research topics was resumed. The group of UDOT stakeholders is known as the Utah Transportation Research Advisory Council (UTRAC) and the annual workshop has come to be known as the UTRAC Workshop. The result has been an increasingly diverse mix of research projects funded. In recent years, nearly all the functional areas of the Department have benefited by the activities of the Research Division.

Another historical factor, an outgrowth of ISTEA legislation, has helped to shape the current UDOT research program. ISTEA supported expansion of the University Transportation Centers program. These centers were to be funded by the US DOT through the FHWA on a regional basis and would be required to develop unique objectives having regional significance.

The FHWA's Region 8 center, known as the Mountain Plains Consortium (MPC), has established rural transportation and distance learning as its themes. The Utah Transportation Center at the University of Utah is affiliated with MPC.

UDOT Strategic Direction

The Research Division makes every effort to align its program with the department's Strategic Direction. The following elements describe UDOT's Strategic Direction.

Mission Statement

Quality Transportation Today, Better Transportation Tomorrow. We connect communities.

Values

Employee Centered

Customer Focus

Quality Service

Great Performance

Strategic Goals

Take Care of What We Have

Focus Areas:

Pavement Preservation

Bridge Preservation

Maintenance Efforts

Make the System Work Better

Focus Areas:

Traffic Management

Traveler Information

Access Management

Improve Safety

Focus Areas:

Roadway Safety

Work Zone Safety

Pedestrian/Bicycle Safety

Increase Capacity

Focus Area:

Add Lanes

Program Development

The aforementioned strategic goals and focus areas can best be achieved by involving our customers in the process of developing the program and generating the products. This assures that their needs and satisfaction are considered at all times. This is achieved through the UTRAC needs identification process as well as through participation by UDOT technical personnel on Technical Advisory Committees (TAC's) that are empowered to help guide each major study undertaken. Because of the number of currently active projects, UTRAC was not held in FY 04 in order to allow the Research staff to concentrate on completing and implementing active projects.

Project Development Objectives:

Excellent Customer Service

Technical Expertise

Effective Training

Continuous Self Improvement

Policies, Procedures, Standards & Specifications

Leadership for Innovative Practices

Building Tomorrow's Systems Today

Research Division Mission Statement

The Research Division is responsible for planning, conducting, coordinating and managing transportation related research and development, and promoting the implementation of beneficial results. The customers of the programs, projects and products generated by the Research Division are the other operating divisions and regions within UDOT as well as other transportation agencies and, of course, end users of the transportation network. The fundamental objectives of the Research Division are reflected in the following mission statement:

Tools for Better Transportation Tomorrow

National Program Services

Literature Searches

The Research Division continues to perform literature searches. The TRIS database is now accessible directly via the internet.

NCHRP and TRB

Since 1969, the National Cooperative Highway Research Program (NCHRP) has played an important part to all state transportation research programs. The Transportation Research Board, (TRB) a division of the National Science Foundation, administers it on behalf of the American Association of State Highway and Transportation Officials (AASHTO), and the Federal Highway Administration (FHWA). Funding contributions are apportioned among the various states as well as the FHWA. The source of contribution can be 100% federal dollars. No state match is required.

The NCHRP program provides four major research functions. These functions include: 1) identification and execution of large studies having national scope and implementation potential; 2) periodic, regular synthesis of topics having national significance; 3) small scale studies requiring immediate response that are identified by individual AASHTO committees through an informal process; and 4) the more recent IDEA/ITS program that focuses on helping promising transportation related technology achieve an implementation status.

The NCHRP has established a history of fostering research activities through a well thought out and balanced process, one that is designed to provide the discipline required to achieve focused, applied, implementable, transportation research while still maintaining the freedom to look outside-the-box to get fresh perspectives and ideas. It is a process that grew up through the same culture and shares many commonalities with that of the Utah Transportation Research Advisory Council (UTRAC). Both solicit participation and ideas from a broad and diverse spectrum of interests and expertise. However, final funding decisions are made by a representative group of transportation oriented technical and managerial experts. Also, individual studies are guided by Technical Advisory Committees (TAC's), at least half of which are made up of transportation stakeholders; but, diverse interest groups are also encouraged to participate.

From a program perspective, it is important to recognize that NCHRP topics are chosen to address scopes of national interest. The value of this major investment is that it agglomerates resources for solving problems at a funding level that would not be possible for most individual states acting alone. However, it is not designed to respond to topics limited to regional or local interest. As a result, it constitutes only a portion of a well-balanced research program. The current Executive Director and Deputy Director of UDOT both recognize the value of leveraging UDOT's contribution to this pooled fund approach.

The Transportation Research Board (TRB) activities focus on topics of national interest. However, its method of operation is different than that of NCHRP. It supports technology transfer through the

volunteer activities of technical committees made up of nationally and internationally recognized experts. These experts bring forth research findings, supported primarily by funding sources external to TRB. These findings are peer reviewed and evaluated by the committee membership. Successful submittals are then presented at formal sessions during an annual meeting and are also published. In addition, the technical committees identify research needs for consideration by other funding agencies.

Some of the results presented are in the realm of basic research relative to transportation issues. Others are focused on applied topics and are immediately implementable. The Transportation Research Board is internationally recognized as the premier forum of transportation related technology transfer.

The funds contributed to TRB are used to sponsor the annual forum that supports this technology transfer. Also, they pay for publication of the peer reviewed technical reports submitted.

The Utah Department of Transportation utilizes the TRB investment in a number of ways. Currently, attendance at the annual meeting is being supported on a rotating basis among various disciplines and divisions within the Department, as well as those that prepare papers and poster presentations. This is advantageous in that, over a long period of time, it exposes the greatest number of people to the technology and process.

NTPEP

UDOT is an active member of the AASHTO National Transportation Product Evaluation Panel (NTPEP). The Research Division represents UDOT as a voting member of the panel. The Department provides labor costs and annual fees for supporting the program. Participation with this national program has the potential to save a significant amount of testing and evaluation costs at the Department level.

Research Division Staff

Research Division's staff information is shown in Table A.

Table A
Research Division Staff

Name	Title	Phone
Shana Lindsey, P.E.	Director of Research	801-965-4196
Doug Anderson, P.E.	Research Project Manager	801-965-4377
Ken Berg, P.E.	Development Engineer	801-965-4321
Dan Hsiao, P.E.	Research Project Manager	801-965-4638
Blaine Leonard, P.E.	Research Project Manager	801-965-4155
Barry Sharp	Research Specialist II	801-965-4314
Michelle Page, P.E.	Research Program Manager	801-965-4333
Abdul Wakil, P.E.	Technology Transfer Engineer	801-964-4455
Esther Olsen	Secretary	801-964-4568
Debbie Heim	Research Technician	801-965-4017
Melodie O'Carroll	Librarian	801-965-4626
Rae Ann Jensen	Archive Specialist	801-965-4656

Research Division Functional Units

The Research Division program is divided into three functional units: research; development, and technology transfer. Research activities attempt to identify the potential of scientific discoveries or improvements in technology, materials and processes to advance the state of the art. UDOT research activities focus primarily on applied rather than basic topics. This means that the results of the research are immediately implementable and would result in improvements to safety or efficiency.

Development includes the evaluation and enhancement of new and existing products and processes and the review of standards, policies and procedures relative to these products and processes. Technology transfer activities include the application and dissemination of the results of research and development, both that sponsored by UDOT as well as other sources. A more detailed description of each of these functional units is described below.

Research Activities

Research activities cover a broad range of objectives dealing with numerous topics, methodologies and degrees of involvement. The over-riding goal is to identify the needs of our internal and external customers, to partner with those customers, and to develop a balanced program that meets their needs.

Historically, research objectives have included measurement of material properties and their longevity, verification of design practices, evaluation of current procedures, application of new technologies and consideration of economic benefits. Topics have included foundations, structures, pavements, roadway geometry, traffic, safety, planning, maintenance, environmental, public transportation and public relations. Methodologies that include literature searches, surveys, synthesis, analysis, physical testing, physical and analytical modeling are all employed where appropriate. Degree of involvement ranges from informal responses to management of large, complex studies.

The Research Unit maintains active contact with the three major engineering colleges in the state and cooperates with other universities and colleges where their research is beneficial to the Department. The Research Unit also interacts with other state highway agencies, the Federal Highway Administration (FHWA), the Transportation Research Board (TRB) and numerous other technical organizations in the identification and performance of research objectives.

New research projects are identified and prioritized by the Utah Transportation Research Advisory Council (UTRAC), primarily through its annual workshop. Projects identified as having the highest priority and potential benefits, within the limitations of funding, are included in the annual Work Program. Projects having national or regional scope are recommended to the NCHRP for funding or are included with other pooled-fund activities. Searches of both published and unpublished literature sources are performed early in the process to avoid duplication and to utilize the work of others wherever feasible.

Once research projects have been identified for funding, Technical Advisory Committees (TAC's) are organized to help refine the work plan and to review the progress and results produced by the study. These committees are made up of potential end users of the technology. They meet at least on a quarterly basis and typically more often during the beginning stages of a project. The Research Unit provides project management functions to monitor progress of the study and coordinate the activities of the principal investigator and the TAC. Some of the more successful recent studies have been performed using a team approach, with both the principal investigator and UDOT personnel contributing to the outcome of the work.

Development Activities

The Research Division has primary responsibility for managing and conducting the new product evaluation process for UDOT. Three staff members, Michelle Page, Ken Berg and Barry Sharp, spend a significant amount of their time managing this process. Vendor requests are submitted on a standardized form, and are reviewed monthly by the New Product Evaluation Panel (NPEP). The Division, documenting the activity in this area, maintains an Accepted Products Listing (APL) and a comprehensive database. Some non-labor funds are also allocated to this activity, which allows for the purchase of products and outside technical services used for evaluation and testing.

Development functions are directed both to the New Products and Experimental Features Programs. These programs serve as a clearinghouse for the evaluation and field testing of new products. In a typical year, UDOT receives 100 or more requests from private vendors to use their products. The Development Unit provides a consistent, unbiased, methodical approach to prioritizing the evaluation and approval of new products.

Development projects are carried out in cooperation with the other divisions within UDOT. During the past year, the New Products Evaluation Panel (NPEP) has been very active. This panel is composed of individuals from the various functional units within UDOT that are concerned with new product evaluation. The panel meets monthly to screen and prioritize review of products based on needs, funding limitations and potential benefits. The activities of this panel are summarized annually in report format.

The 'Accepted' Products Listing (APL) and the 'Performance Data' Products Listing (PDPL) are published as a result of decisions made by NPEP.

Selected products are occasionally evaluated on small-scale test sections called *Experimental Features*. These items are placed in the field for demonstration purposes. The test sections typically address concerns such as installation, handling, construction and durability prior to general approval of a product. The results of these findings are published annually in interim and/or final reports. The list of current active Experimental Features are shown in the following table.

Abdul Wakil of the Research Division has the primary responsibility for technology transfer initiatives. Results are promoted through publication, development of new standards, approved product listings, specifications, procedures, workshops, literature searches, video conferencing and other means. Newsletters are published periodically to help keep UDOT employees and other research associates across the country updated on research activities. Another key element of the technology transfer program is the review and dissemination of information that is obtained from other research agencies via hard copy publications and electronically.

Workshops and/or training sessions are facilitated and sponsored by the Research Division when needed to implement study findings or promote new technology.

Funding

As of Aug. 19, 2002, 23 CFR was revised to stipulate that the costs to administer the State Planning & Research work program cannot be directly charged, but, can, however, be allocated to research projects and recovered as part of the cost of each project. These administration costs for the coming fiscal year are estimated, prorated and included in each research project budget.

The following four tables represent the projected FY06 budget with some carryover represented in FY07 and FY08. Table 1 is an all-inclusive summary of commitments to date with references to Tables 2-6.

Table 1: RESEARCH SPR Funds For FYO6 Work Program

SPR Funds		Amount					
Available obligated		\$861,386					
Future unobligated (est.)		\$1,457,307					
Use unobligated to cover SPR 02 overages due to cost allocation		<u>\$11,276</u>					
TOTAL SPR AVAILABLE		\$2,307,417	1				

Note: LTAP Funds are pulled prior to establishment of the Research Budget since it is a required federal program.

FYO6 SPR PROGRAM COSTS						
TIG	\$5,000					
TRB	\$75,000					
NTPEP	\$6,000					
NCHRP	\$159,600					
FHWA Peer Exchange	<u>\$5,000</u>					
TOTAL PROGRAM COSTS	\$250,600	2				

POOLED FUND LEAD STATE COSTS	Budget	Previous FY's	FY06	FY07	FY08	Project Manger
Pavement Marking Life Cycle						Ken Berg
WASHTO X						Doug Anderson
Dynamic Passive Pressure on Abutments and Pile Caps	\$75,000		\$40,000	\$35,000		Daniel Hsiao
TOTAL POOLED LEAD STATE COSTS	\$75,000		\$40,000	3	\$35,000	

POOLED FUND NON LEAD STATE COSTS	Budget	Previous FY's	FY06	FY07	FY08	Lead Agency
TCCC Training Management & Development	\$60,000	\$20,000	\$20,000	\$20,000		FHWA
Western Alliance for Quality Transportation Construction	\$40,000	\$20,000	\$10,000	\$10,000		Alaska
Evaluation of the Safety Edge	\$45,000	\$15,000	\$15,000	\$15,000		FHWA
Traffic Management Center	\$100,000	\$25,000	\$25,000	\$25,000	\$25,000	FHWA
Aurora Program	Ongoing	\$25,000	\$25,000	\$25,000	\$25,000	FHWA
Western Transportation Institute—Evaluation of Road Weather Information System Program at UDOT (Subset of Aurora program with UDOT as lead state)	\$20,000		\$20,000			Utah
Demonstration and Evaluation of ITS Technology for The rural Highway Environment a.k.a. "FRONTIER"	\$20,000		\$10,000	\$10,000		Montana
Evaluation of Low Cost Safety Improvements	\$150,000		\$150,000			FHWA
TOTAL POOLED FUND NON LEAD STATE		\$105,000	\$275,000	4	\$105,000	\$50,000

CURRENT SPR PROJECT COSTS (See attached)	Budget	Previous FY's	FY06	FY07	FY08	
TOTAL TO COMPLETE CURRENT SPR PROJECTS	\$1,519,083	\$303,262	\$749,678	5	\$575,405	\$194,000
Research PM's						

NEW UTRAC PROJECT COSTS (See attached)	Budget	Previous FY's	FY06	FY07	FY08	
TOTAL TO COMPLETE NEW UTRAC PROJECTS	\$1,366,518		\$769,477	6	\$247,000	\$65,000

SPR FY06 SUMMARY	\$2,307,417	SPR Available	1
	\$250,600	FY06 SPR Program Costs	2
	\$40,000	FY06 Lead Pooled Fund Costs	3
	\$275,000	FY06 Non-Pooled Fund Costs	4
	\$749,678	FY06 Current SPR Projects	5
	\$769,477	Est. FY06 UTRAC Commit.	6
	\$450,000	Anticipated Carryover SPR	
	\$450,000	75% of Personal Services (Overhead)	
	\$157,242	Misc. Personal Services (Office Costs)	
	\$9,335	Travel Annual Budget	

\$56,085	Remaining After Total Expenditure/Commitments for FY06
	(Contingency for Additional Pool Fund Requests, Special Studies, Contract Mods, Travel, Etc.)

Table 2: RESEARCH STATE FUNDS For FY06 Work Program

STATE FUNDS	AMOUNT
FY06 State Funds (est.)	\$492,700
FY06 UTRAC Funds Committed	\$72,000
Est. to Complete Current State Project Costs (See Attached)	\$176,752
25% of Personal Services (Overhead)	<u>\$150,000</u>
TOTAL STATE AVAILABLE FOR FY06	\$93,948

Table 3: CURRENT SPR PROJECT COSTS

DESCRIPTION	ORIGINAL ESTIMATE	CURRENT ESTIMATE TO COMPLETE	PREVIOUS FY's	FY 06	FY 07	FY 08
DOWN-DRAG OF PILES	\$30,000	\$59,000		\$45,000	\$14,000	
BRIDGE SCOUR COUNTERMEASURES Phase II	\$45,000	\$45,000		\$12,000	\$29,000	\$4,000
BRIDGE DECK STRATEGY	\$45,000	\$45,000	\$26,000	\$19,000		
DEVELOP UTAH WETLANDS ASSESSMENT METHOD	\$55,000	\$44,500	\$18,143	\$26,357		
LONG TERM MONITORING OF I-15 EMBANKMENT	\$150,000	\$225,000		\$70,000	\$70,000	\$85,000
PREVENTABLE DECK JOINT & SURFACE TREATMENTS STRATEGY	\$80,000	\$132,815	\$5,000	\$105,000	\$22,815	
EVAL. TRAFFIC & SAFETY INITIATIVES (CONTRACT EXTENSION)	\$90,000	\$49,425	\$49,425	\$49,425		
PRIORITIZATION OF IMPORTANT ROUTES (CRITICAL LIFELINES)	\$90,000	\$90,000			65,000	\$25,000
IMPLEMENTATION OF AASHTO DESIGN GUIDE	\$155,000	\$79,180		\$39,590	\$39,590	
WEB-DELIVERED PAVEMENT & TRAFFIC DATA	\$43,000	\$14,556	\$28,444	\$14,556		
N/D EVAL. METHOD FOR STRESS IN GIRDERS	\$175,000	\$180,000		\$50,000	\$100,000	\$30,000
HEALTH MONITORING OF I-15 STUCTURES	\$140,000	\$210,000		\$70,000	\$90,000	\$50,000
MATERIALS CHARACTERIZATION FOR THE AASHTO 2002 PAVE DESIGN GUIDE	\$150,000	\$150,000		\$75,000	\$75,000	
UTAH LTPP MONITORING	\$50,000	\$50,000		\$35,000	\$15,000	
IMPACTS OF RAISED MEDIANS	\$70,000	\$20,000	\$50,000	\$20,000		
MONITORING SPLICED GIRDERS, DECK PANEL, JOINTS & FRP RETROFIT	\$30,000	\$25,000	\$5,000		\$25,000	
MONITOR MSE WALLS, PHASE 2	\$80,000	\$60,000	\$20,000	\$30,000	\$30,000	
LOAD RATE ON AXIAL AND LATERAL PILE CAP	\$150,000	\$70,000	\$80,000	\$70,000		
ROCKFALL HAZARD RATING SYSTEM	\$40,000	\$18,750	\$21,250	\$18,750		
TOTALS	\$1,668,000	\$1,568,226	\$303,262	\$749,678	\$575,405	\$194,000

Table 4: NEW UTRAC PROJECT COSTS
(2005 UTRAC PROBLEM STATEMENT SUMMARY LIST – PRIORITIZED FOR FUNDING)

FUNDING PRIORITY	PROB NO.	PROBLEM TITLE	SUBMITTED BY	CHAMPION	PROJECT MNGR	SCHEDULE	APPROX BUDGET	YEAR 1 BUDGET	YEAR 2 BUDGET	YEAR 3 BUDGET	FUNDING SOURCE	STATE FUNDING	FED. FUNDING
1	05.01-1	Mitigate Queue Lengths in Work Zone Traffic Control	Darrell Giannonatti and Doug Anderson	Pete Negus	Blaine L	Oct 05 due	\$50,000	\$50,000			SPR		\$85,250
2	05.02-02	Cost-effectiveness & Indicators-pavement Rejuvenation	Scott Nussbaum	Scott Nussbaum	Barry Sharp	3 Year Study	\$80,000	\$30,000	\$30,000	\$20,000	SPR		\$51,150
3	05.03-4	Full-Depth Recycling and Stabilization of Pavement Base Layers	Spencer Gutherie and Nathan Lee	Nathan Lee	Doug A.	2 Year	\$100,000	\$50,000	\$50,000		SPR		\$85,250
4	05.04-6	Design Methods for Unique Culvert Installations	William Grenney	Denis Stuhff	Michelle P.		\$35,000	\$35,000			SPR		\$59,675
5	05.05-7	Extract Vehicle Classification from TOC Video	Chris Glazier	Chris Glazier and Richard Manser	Doug A.		\$73,077	\$73,077			SPR		\$124,596
6	05.06-6	Advanced Warning Signal Site Selection Evaluation Matrix	Mack Christensen and Grant Shultz	Mack Christensen	Shana L.	9-12 Months	\$35,000	\$35,000			SPR		\$59,675
7	05.07-3	Dynamic Passive Pressure on Abutments & Pile Caps	Kyle Rollins and Gerber (BYU)	Biscoff/Boyle /Sjoblom	Dan. H	2 Years	\$75,000	\$40,000	\$35,000		SPR/Pooled		\$68,200
8	05.08-1	Improvement of Deck Concrete Mix Design and Curing Practices	Barr, Halling and Ryan USU	Todd Jensen	Dan H	2-3 Years	\$70,000	\$35,000	\$30,000	\$5,000	SPR		\$59,675
9	05.01-3	Worker Visibility	Darrell Giannonatti and Doug Anderson	Darrell Giannonatti	Michelle P.	Oct. 5 due	\$25,000	\$25,000			State	\$42,625	
10	05.02-06	Skid Index Trigger Values	Lloyd Neeley	Bill Lawrence	Barry S.		\$10,000	\$10,000			SPR		\$17,050
11	05.03-1	Asphalt Binder Uniformity	Cameron Petersen	Kevin Van Frank	Doug A.		\$100,000	\$100,000			SPR/Pooled		\$170,500
12	05.04-2	Bridge Scour Countermeasure Phase II	Michael Fazio	Michael Fazio, Denis Stuhff, Tim Ularich	Dan H.	2 Year	\$42,000	\$30,000	\$12,000		SPR		\$51,150
13	05.05-3	Access Management Performance Index	Tim Boschert, Grant Shultz (BYU)	Tim Boschert	Michelle P.		\$35,000	\$35,000			SPR		\$59,675
14	05.06-7	Access Management/Traffic Impact Analysis Training	Tim Boschert, Grant Schultz	Tim Boschert	Shana L.	12 Months	\$30,000	\$30,000			SPR		\$51,150

15	05.07-2	Programming of Strong Ground Motion Instrumentation of New Bridges	Marv Halling (USU)	Jim Higbee	Blaine L	1 Year	\$30,000	\$30,000			SPR		\$51,150
16	AM.05 .001	Evaluation of Effects of Stay in Place Forms on Bridges	Wadsworth Construction	Todd Jensen	Dan H.	1 Year	\$50,000	\$50,000			SPR		\$85,250
17	05.04-1	Design & Development of a Context Sensitive Visual Resource Assessment and Management (VRAM) System for UDOT	Terry Johnson	Terry Johnson and Lars Anderson	Michelle P.	2 Years	\$88,000	\$44,000	\$44,000		SPR		\$75,020
18	05.02-07	Targeted and Adaptive Simulator Training for Winter Maintenance	David Strayer	Richard Clarke and Shana Lindsey	Shana L	6 Months	\$9,900	\$9,900			SPR		\$16,880
19	05.05-11	Determination of Crash Costs for Use in Benefit/Cost Analysis (Value of Life)	Jim McMinnimee & Doug Anderson	Jim McMinnimee	Doug A.		\$25,000	\$25,000			SPR		\$42,625
20	AM.05 .002	Evaluation of Rapid Mapper Technology		Lisa Wilson	Angelo P.		\$42,000	\$42,000			State	\$71,610	
21	AM.05 .003	Older Driver Study: Evaluation of Safety Effects of pavement Markings and Signage			Shana L	2 Years	\$80,000		\$40,000	\$40,000	SPR		
22	AM.05 .004	Pavement Marking Study (Test Sections)		Shana L.	Shana L. and Michelle P.	8 Months	\$5,000	\$5,000			State	\$8,525	
23	05.05-10	Good Roads Cost Less	Gary Kuhl	Kim Schvaneveldt	Abdul W.	6 Months	\$20,000	\$20,000			SPR		\$34,100
24	05.03-3	SMA Paving Mechanistic Properties	Rodney Terry	Rodney Terry	Doug A.	2 Years	\$100,000	\$50,000	\$50,000		SPR		\$85,250
25	05.07-6	Geophysical methods to prioritize mitigation options for SR-9 in the Coal Hill landslide area.	Francis Ashland UGS	Leslie Heppler	Blaine L.		19,500	\$19,500			SPR		\$33,248

Note: Highlighted studies will be postponed unless additional money becomes available.

Table 5: CURRENT STATE PROJECT COSTS

DESCRIPTION	BUDGET	ESTIMATE TO COMPLETE	PREVIOUS FY's	FY 06	FY 07	FY 08
EVALUATE WORK ZONE TRAVELER INFO.SYS.	\$80,000	\$61,400		\$50,000	\$11,400	
DYNAMIC CHARACTERISTICS OF NEW BRIDGES	\$109, 000	\$53,850	\$15,000	\$38,850		
STRONG MOTION INSTRUMENTATION OF BRIDGE SITE	\$80,000	\$17,750		\$5,902	\$5,902	\$5,902
ADAPTIVE SIGNAL CONTROL IMP & EVAL	\$40,000	\$60,000		\$60,000		
EFFECTIVENESS OF HOV LANES, PH 3	\$29,000	\$43,500	\$38,500	\$5,000		
UTAH INTERSECTION SAFETY	\$45,000	\$67,500	\$62,500	\$5,000		
SMART PDA	\$12,000	\$12,000		\$12,000		
TOTALS	\$440,000	\$383,455	\$116,000	\$176,752	\$17,302	\$5,902

Table 6: I-15 Test Bed Funds

Phase 1:	Programmed Amount:		
	TEA-21 (incl. 20% State Match)	\$250,000	
	Total Phase 1 program		\$250,000
	Costs to Date	(\$182,930)	
	Balance	\$67,0700	
	Estimate to Complete	\$0	
	Estimated remaining Phase 1 program		\$67,070
Phase 2:	Programmed Amount:		
	TEA-21 (incl. 20% State Match)	\$1,500,000	
	Total Phase 2 program		\$1,500,000*
	Costs to Date	(\$1,454,357)	
	Balance	\$45,643	
	Estimate to Complete	\$71,478	
	Estimated remaining Phase 2 program		(\$25,835)**
* - Other state, private, and pooled-fund funding sources were initially programmed and have been expended.			
** - Will be covered with Phase 1 remaining programmed amount			
Phase 3:	Programmed Amount:		
	TEA-21 (incl. 20% State Match)	\$937,500	
	FY 03 SPR	\$280,000	
	FY 05 SPR	\$563,600	
	Total Phase 3 program		\$1,781,100
	Costs to Date	(\$1,250,600)	
	Balance	\$531,100	
	Estimate to Complete	\$531,100	
	Estimated remaining Phase 3 program		\$0
Phase 4:	Programmed Amount:		
	TEA-21 (incl. 20% State Match)	\$1,000,000	
	FY 05 State	\$300,700	
	FY 05 SPR	\$222,100	
	Total Phase 4 program		\$1,522,800
	Costs to Date	(\$546,492)	
	Balance	\$976,308	
	Estimate to Complete	\$976,308	
Estimated remaining program		\$0	

Table 7 shows the current Innovative Bridge Projects, each of which are separate federal grants. Details of the active Innovative Bridge projects are shown in the Project Status Sheets.

Table 7: Innovative Bridge Funds

Description	Prog. Amt.	Costs To Date	Balance	Est. to Complete ¹
Stainless Clad Rebar Rt. 79 MP 2, Weber Co.	\$68,500	\$44,500	\$24,000	\$24,000
I-80, Co. Rd. Over I-80, 1.9 Miles E. of Wanship, Precast Deck	\$175,615	\$130,866	\$44,749	\$44,749
R-2, I-215 Over 3760 S. & 3900 S.	\$55,000	\$29,411	\$25,589	\$25,589

1 - Includes state match and 26% allocation of administrative costs.

Completed Projects

Table 8 shows projects completed within the FY05.

Table 8: Completed Projects

Fund Source	CHARGE ID	DESCRIPTION
SPR	81FR0032	DEEP DYNAMIC COMPACTION STUDY
SPR	81FR0033	UPDATE "GOOD ROADS COST LESS"
SPR	81FR0140	IMPLEMENTATION OF SMART PDA
SPR	81FR0141	SURFACE RESPONSE SPECTRA (PEER REVIEW OF GENERAL PROCESS)
SPR	81FR0141	SURFACE RESPONSE SPECTRA GENERAL PROCESS
SPR	81FR0141	SURFACE RESPONSE SPECTRA (LIQUEFACTION)
SPR	81FR0143	LOWER SPEED WORK/NON WORK ZONES
SPR	81FR0211	DOWNHOLE ARRAY AT 1-15/2100 S.
SPR	81FR0220	VIDEO BASED TRAFFIC CLASSIFICATIONS PH. 2
SPR	81FR0276	EVALUATION OF I-15 DESIGN/BUILD PROJECT
SPR	81FR0276	REVIEW EVALUATION OF I-15 DESIGN/BUILD PROJECT
SPR	81FR0333	ASSESS USER IMPACTS OF FAST TRACK CONSTRUCTION
SPR	81FR0345	PERFORMANCE BIDDING FOR ASPHALT PAVEMENTS
SPR	81FR0131	ALTERNATIVE AVALANCHE CONTROL AMMUNITION
SPR	81FR0292	LONG TERM MONITORING OF I-15 EMBANKMENT PERFORMANCE-GEOFOAM
STATE	81SR0011	CRASH DATA AVAILABILITY
STATE	81SR0123	EVAL. SAMPLE DISTURBANCE FROM SHELBY TUBE VS. PISTON SAMPLERS & MSE EVAL.
STATE	81SR0211	ADAPTIVE SIGNAL CONTROL PH 2
STATE	81SR0212	AUTO MEASURES OF EFFECTIVENESS OF ATMS
STATE	81SR0213	EFFECTIVENESS OF HOV LANES PH 1
STATE	81SR0222	AIR QUALITY HOT SPOTS
STATE	81SR0223	IMPROVE ACCURACY OF DESIGN DISCHARGE CALCULATIONS
STATE	81SR0272	DEVELOPMENT OF PROTOTYPE CULVERT DATABASE FOR CULVERT COND. STUDY
STATE	81SR0291	BMP ROCKFALLS PH 1 (PRELIM. RATING)
STATE	81SR0291	BMP ROCKFALLS PH 2, PART 1 (DETAILED RATING)
STATE	81SR0293	REPAIR OVERHEAD ALUMINUM SIGN
STATE	81SR0358	EXPECTED ACCIDENT RANGE OF HIGHWAY FUNCTIONAL CLASS
STATE	81SR0354	AUTO. DATA COLLECTION ANALYSIS
STATE	81SR0355	DETECTOR TECHNOLOGY EVALUATION
STATE	81SR0356	EVAL. EFFECT DILEMMA ZONE OF ADVANCED SIGNAL WARNING
STATE	81SR0361	NOISE REDUCTION ON I-215 FOLLOW-UP
STATE	81SR0363	EQ DRAIN CANLEX TEST
TB2T	81F15023	LATERAL LOADS ON PILE GROUPS PH 3
TB3	81F15306	LONG TERM EVALUATION OF FRP FOR BRIDGE RETROFIT
TB4	81F15402	DOWNHOLE ARRAY AT I-15/2100 S.
TB4	81F15408	ASSESS USER IMPACT OF FAST TRACK CONSTRUCTION
TB4	81F15409	I-15 TECHNOLOGY TRANSFER WORKSHOP
PFLS	4001808H	PAVEMENT MARKING LIFE CYCLE PH 1
PFLS	4002708H	LATERAL LOADS ON PILE GROUPS
SPR	81FR0218	UTAH CORRIDOR PRESERVATION STUDY
SPR	81FR0232	CONDITION OF EXISTING HIGHWAY CULVERTS AND DETERMINATION OF PERFORMANCE MEASURES

SPR	81FR0237	LOCATION OF RWIS ENVIRONMENTAL STATIONS
SPR	81FR0344	SIMULATOR TRAINING FOR WINTER MAINTENANCE
TB2	81F15022	EVALUATION OF GEOPIER FOUNDATIONS SYSTEMS, PH. 2
TB3	81F15307	ULTIMATE AND RESIDUAL CAPACITY OF GEOPIER FOUNDATIONS SUBJECTED TO UPLIFT AND COMPRESSION LOADS (GEOPIER FOUNDATIONS, PH. 3)
SPR	81FR0292	LONG TERM MONITORING OF I-15 EMBANKMENT PERFORMANCE, PH. 1
TB2	81F15022	EVALUATION OF GEOPIER FOUNDATION SYSTEMS, PH. 2
TB3	81F15307	ULTIMATE AND RESIDUAL CAPACITY OF GEOPIER FOUNDATIONS SUBJECTED TO UPLIFT AND COMPRESSION LOADS (GEOPIER FOUNDATIONS, PH. 3)
SPR	81FR0344	SIMULATOR TRAINING FOR WINTER MAINTENANCE
TB3	81F15302	EXPERIMENTAL DETERMINATION OF DYNAMIC CHARACTERISTICS OF NEW BRIDGES (FORCED VIBRATION, PH. 3)
TB3	81F15303	LONG TERM STRUCTURAL MONITORING OF POST-TENSIONED SPLICED GIRDERS AND DECK JOINTS
TB4	81F15406	EVALUATION OF FIBER REINFORCED POLYMER COMPOSITE CONFINED RECTANGULAR CONCRETE COLUMNS
SPR	81FR0142	SCOUR COUNTERMEASURE STUDY, PH. 1
SPR	81FR0210	BRIDGE DECK STRATEGY
STATE	81SR0350	HYDRAULIC DISCHARGE CALCULATIONS, PH. 2 (FREQUENCY)
STATE	81SR0441	HYDRAULIC DISCHARGE RECALCULATIONS, PH. 2 (CANYONS)
SPR	81FR0333	FAST TRACK CONTRACTING
STATE	81SR0341	CRASH DATA DELIVERY USING GIS, PH. 2
STATE	81SR0359	SMART PDA-SOFTWARE DEVELOPMENT

Key:
STATE State
SPR State Planning & Research
PFLS Pooled Fund Lead State
IB Innovative Bridge
TB__ I-15 Test Bed, Phase ____

Note: The following sections contain Project Status Sheets on all active projects.

SPR FUNDED STUDIES

THIS PAGE LEFT BLANK INTENTIONALLY

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Evaluate Traffic and Safety Initiatives																	
Fund. Source	SPR	Project Type	Traffic & Safety															
Charge ID	81FR0341	Performing Org.	BYU															
PIC	UT02.401	Contract No.	03-9153															
Project Mgr.	Lindsey	Contract Start Date	2/15/2003															
Princ. Inv.	Saito	Contract End Date	2/15/2005															
FISCAL																		
Contract Amt.	\$83,000	Contract Cost to Complete	\$32,950															
Contract Cost to Date	\$50,050	Project Cost to Complete	\$42,835															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
On schedule																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Review TAC Rec	Est.																
		Act.																
2	Goal of STUDY Long term	Est.																
		Act.																
3	Literature review	Est.																
		Act.																
4	Public survey on Udot's ATIS	Est.																
		Act.																
5	Improvement recommendation	Est.																
		Act.																
6	Forecasting methods	Est.																
		Act.																
7	Functionality and system interfaces	Est.																
		Act.																
8	Real time Traffic reassignment	Est.																
		Act.																
9	Final report	Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Down-drag of Piles																	
Fund. Source	SPR	Project Type	Research Project															
Charge ID	81FR9968	Performing Org.	Brigham Young University															
PIC	UT98.504	Contract No.	05-9112															
Project Mgr.	Leonard	Contract Start Date	8/1/04															
Princ. Inv.	Rollins	Contract End Date	2/1/06															
FISCAL																		
Contract Aml.	\$45,327	Contract Cost to Complete	\$45,327															
Contract Cost to Date	\$0	Project Cost to Complete	\$58,925															
OBJECTIVE																		
Settlement of fills in embankment for bridge foundations often cause skin friction of the piles. This skin friction can decrease the structural load capacity of the piles. Engineers on the I-15 project considered the skin friction question the major unknown affecting pile performance, potentially increasing foundation costs by 50% or more. This project will gather full scale field data to improve our understanding of these downdrag forces, based on pile instrumentation at two sites.																		
IMPLEMENTATION PLAN																		
Verify the magnitude and nature of downdrag forces and modify our design procedures accordingly. Modify the geotechnical and structural manuals of instruction with this updated design information for use on future projects.																		
STATUS																		
Pile instrumentation and data gathering is underway. Coordinating pile driving with contractors on two project sites: I-15 in Springville and the Salt Lake International Airport.																		
TASK PROGRESS TABLE																		
NO.	TASK		2004				2005				2006				2007			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Install instruments	Est.																
		Act.																
2	Soil testing	Est.																
		Act.																
3	Measure axial force vs. settlement	Est.																
		Act.																
4	Evaluate methods	Est.																
		Act.																
5	Final report preparation	Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Hydrodynamic Separators as Stormwater Best Management Practices																	
Fund. Source	SPR	Project Type				Hydraulics/Environmental												
Charge ID	81FR0215	Performing Org.				Stantech Consulting Inc.												
PIC	UT01.306	Contract No.				04-9130												
Project Mgr.	Wakil	Contract Start Date				2/13/2004												
Princ. Inv.	Nichols	Contract End Date				4/13/2005												
FISCAL																		
Contract Amt.	\$49,526	Contract Cost to Complete				\$0												
Contract Costs to Date	\$49,526	Project Cost to Complete				\$0												
OBJECTIVE																		
This project consists of the preparation of a selection methodology and a performance-based specification for oil-water separator devices. Presently, UDOT does not have a standard for designing, selecting, installing or maintaining these types of devices. It would help designers if a standard selection methodology was available to help in choosing an appropriate oil-water separator for transportation projects.																		
IMPLEMENTATION PLAN																		
UDOT Special Provision for Designing and Selecting Oil-Water Separator																		
STATUS																		
This project is completed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Identify typical pollutants and average concentrations	Est.																
		Act.																
2	Evaluate hydrological characteristics	Est.																
		Act.																
3	Review existing UDOT information and meet with Technical Advisory Committee	Est.																
		Act.																
4	Identify technical/performance data from manufactures and State DWO	Est.																
		Act.																
5	Prepare Selection Methodology	Est.																
		Act.																
6	Prepare performance Specification and Final Report	Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																						
Title		Develop Utah Wetlands Functional Assessment Method																				
Fund. Source	SPR	Project Type				Environmental																
Charge ID	81FR0214	Performing Org.				Utah State University																
PIC	UT01.301	Contract No.				04-9044																
Project Mgr.	Leonard	Contract Start Date				1-Apr-03																
Princ. Inv.	Johnson	Contract End Date				1-Jul-06																
FISCAL																						
Contract Amt.	\$50,930	Contract Cost to Complete				\$34,206																
Contract Cost to Date	\$16,724	Project Costs to Complete				\$44,468																
OBJECTIVE																						
To develop a wetlands assessment method specific to the conditions in Utah, based on the current Montana methodology. The assessment method will take into considerations wetland quality or functional value, including water quality, flood storage, contiguous or isolated waters, wildlife habitat, food chain support, and sediment control, rather than just total acreage. The method will be a logical, time efficient, analytical, reproducible evaluation technique for use in Utah, yielding more sustainable wetlands. It must be accepted by the Army Corps of Engineers.																						
IMPLEMENTATION PLAN																						
A Manual of Instruction will be developed for the new method, and Army Corps of Engineers approval will be sought for the Manual. Forms will be developed for use with the technique. Potential users of the method within UDOT and related outside organizations will be involved in the process and will be familiar with the method as it is developed. Two training sessions will be held for UDOT personnel and consultants to provide full instruction on the use of the method. The method will become the primary tool for wetland assessment on UDOT projects.																						
STATUS																						
Project Underway. Field review of wetland classification types has been completed. Workshop with users and agencies has been held to evaluate various aspects of the proposed method. Manual of Instruction nearly completed. Training session has been completed. Corps mandated additional field testing & verification to insure the uniform application of the method. Contract was modified accordingly to include phases 3 through 6 and the field testing is being planned.																						
TASK PROGRESS TABLE																						
NO.	TASK		2002				2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1-3	Literature Review, coordination with Montana DOT, Revised Problem Statement	Est.																				
		Act.																				
4-6	Identify Wetland Classifications and Functional Unit Criteria for Utah, coordinate with US Army Corps of Eng., Draft Manual of Instruction	Est.																				
		Act.																				
7	Army Corp of Engineers Interim Approval	Est.																				
		Act.																				
8-10	Finalize Manual of Instruction and Standardized Forms, prepare final report	Est.																				
		Act.																				
11	Training Sessions for UDOT and Consultants	Est.																				
		Act.																				
Phase III	Field Testing the UDOT Method by outside groups (UWAG)	Est.																				
		Act.																				
Phase IV	Field Testing five other Methods for comparison	Est.																				
		Act.																				
Phase V	Field testing the UDOT Method by UDOT Staff	Est.																				
		Act.																				
Phase VI	Evaluation of Field Test Results, Presentation of findings and final report	Est.																				
		Act.																				
		Est.																				
		Act.																				

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Condition of Existing Highway Culverts and Determination of Performance Measures																	
Fund. Source		Project Type																
Charge ID	81FR0232	Performing Org.	Simpson, Gumpertz & Heger															
Project No.		Contract No.	#03-9097															
Project Mgr.	B. Leonard	Contract Start Date	25-Sep-02															
Princ. Inv.	T. McGrath	Contract End Date	30-Jul-04															
FISCAL																		
Budget (orig.)	\$156,700	Est. cost to Complete																
Costs to date		Est. Current FY Cost																
OBJECTIVE																		
Assess culverts throughout the state to:																		
<ul style="list-style-type: none"> determine the condition of existing highway culverts and storm drains with spans of two to five feet, develop a system of qualitative and quantitative measures to assess both the short- and long-term performance of highway culverts and storm drains, determine the performance measures which affect and predict performance, and make recommendations to the UDOT on better methods to track and monitor the performance of highway culverts and storm drains. 																		
IMPLEMENTATION PLAN																		
Provide a new database tool which supports the continued inspection and evaluation of culverts, review and update design criteria and specifications relative to culvert installation, and recommend a maintenance program for culverts.																		
STATUS																		
Project completed. Final report UT-04.05 "Condition Assessment of Highway Culverts and Determination of Performance Measures." Implementation underway including modifications to culvert specifications.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Start up / Review Database	Est.																
		Act.																
2	Identify List of Target Culverts	Est.																
		Act.																
3	Detailed Work Plan for Inspection, Assessment	Est.																
		Act.																
4	Interim Report	Est.																
		Act.																
5	Field Surveys	Est.																
		Act.																
6	Analysis of Findings	Est.																
		Act.																
7	Update UDOT Database	Est.																
		Act.																
8	Final Report	Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Long Term Monitoring of I-15 Embankment Performance, Ph. 2																	
Fund. Source	SPR	Project Type				Geotechnical												
Charge ID	81FF0292	Performing Org.				University of Utah												
PIC	TB98.029	Contract No.				pending												
Project Mgr.	Leonard	Contract Start Date				1-Jul-05												
Princ. Inv.	Bartlett	Contract End Date				31-Dec-08												
FISCAL																		
Contract Amt. (est.)	\$150,000	Contract Cost to Complete				\$150,000												
Contract Cost to Date	\$0	Project Cost to Complete				\$195,000												
OBJECTIVE																		
Monitor the performance of embankments in several locations along the I-15 Reconstruction corridor, including embankments constructed with MSE walls over native soils treated with lime-cement columns, embankments constructed over wick-drain treated areas, embankments constructed using lightweight EPS Geofoam, and other innovative construction types. Monitor long-term consolidation of soft clay subsoils subjected to these embankment loads. Model the deformations of the subsoils and evaluate the consolidation properties of these soils. This is the second phase of this monitoring work.																		
IMPLEMENTATION PLAN																		
Develop guidelines for the future construction of embankments over soft soils and the evaluation of soil properties for these soft soils.																		
STATUS																		
Monitoring equipment was installed during the I-15 embankment construction and a report prepared documenting that installation. Instruments continue to be read on a regular basis, and the data evaluated. Report published: UT-03.17:"Geofoam Fill Performance Monitoring", Aug 03. GIS database of installed instrumentation and related geotechnical data has been completed. Reports which have been prepared to document embankment performance include : UT-04.18:"Numerical Modeling of Settlement Behavior of Treated and Untreated Foundation Soils Underlying MSE walls for the I-15 Reconstruction Project, SLC, Utah", and UT-03.20:"Estimation of Preconsolidation Stress and Compression Ratio from the Field and Laboratory Measurements from the I-15 Reconstruction Project", and UT-04.19: "Monitoring and Modelling of Innovative Foundation Treatment and Embankment Construction Used on the I-15 Reconstruction Project, Project Management Plan and Instrumentation Installation Report.", and UT-04.20:"Estimation of Consolidation Properties from In-Situ and Laboratory Testing."																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Monitoring of embankment performance	Est.																
		Act.																
2	Analysis of field data	Est.																
		Act.																
3	Final report and recommendations	Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																			
Title	Long Term Monitoring of MSE Walls																		
Fund. Source	SPR	Project Type	Geotechnical																
Charge ID	81FR0592	Performing Org.	USU																
PIC	TB00.308	Contract No.	pending																
Project Mgr.	Leonard	Contract Start Date	pending																
Princ. Inv.	Bay	Contract End Date	pending																
FISCAL																			
Contract Aml.	pending	Contract Cost to Complete	\$40,000																
Contract Cost to Date	\$0	Project Cost to Complete	\$52,000																
OBJECTIVE																			
Continue to monitor the performance and long term deformation of MSE walls at I-15 and 3600 S. This is the second phase of a project to evaluate these innovative walls and their effectiveness.																			
IMPLEMENTATION PLAN																			
Develop guidelines for the future design and construction of MSE walls over soft soils.																			
STATUS																			
Scope of work still pending.																			
TASK PROGRESS TABLE																			
NO.	TASK		2005				2006				2007				2008				
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	
		Est.																	
		Act.																	
		Est.																	
		Act.																	
		Est.																	
		Act.																	
		Est.																	
		Act.																	
		Est.																	
		Act.																	
		Est.																	
		Act.																	
		Est.																	
		Act.																	
		Est.																	
		Act.																	

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Assessment and Prioritization of UDOT Lifelines and Identification of Critical Bridges																	
Fund. Source	SPR	Project Type				Structures												
Charge ID	B1FR0342	Performing Org.				pending												
PIC	UT02.501	Contract No.				pending												
Project Mgr.	Berg	Contract Start Date				pending												
Princ. Inv.	pending	Contract End Date				pending												
FISCAL																		
Contract Amt.	pending	Contract Cost to Complete				#VALUE!												
Contract Costs to Date	\$0	Project Cost to Complete				#VALUE!												
OBJECTIVE																		
1. Identification and ranking of UDOT corridors that are critical lifelines in Utah.																		
IMPLEMENTATION PLAN																		
The data would be used to more effectively allocate resources for maintenance activities on existing structures. Other UDOT groups could also use the data in the design process and other decision making processes.																		
STATUS																		
The Structures Division is interested in outsourcing the work to a private consultant and is currently evaluating possible firms to offer proposals.																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Literature search	Est.																
		Act.																
2	Coordinate with other agencies to assess similar work.	Est.																
		Act.																
3	Review the information available in UDOT's bridge database	Est.																
		Act.																
4	Review UDOT's available GIS information. Identify every location of schools, hospitals, churches, airports, fire stations, etc.	Est.																
		Act.																
5	Establish criteria for ranking lifeline criticality, including emergency responses, health care, airport access, military facilities, user costs, significant economic impact, key utilities, and available detours.	Est.																
		Act.																
6	Review the criteria with UDOT stakeholders	Est.																
		Act.																
7	Develop a map of those critical bridges and a list of bridges in priority order.	Est.																
		Act.																
8	Incorporate critical routes into PONTIS database. (UDOT task)	Est.																
		Act.																
9	Coordinate with Planning and Asset Management to incorporate criticality designations into their systems.	Est.																
		Act.																
10	Modify Structures Manual of Instruction to incorporate critical rankings into the design process.	Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title		Evaluate Traffic and Safety Initiatives																
Fund. Source	SPR	Project Type				Traffic & Safety												
Charge ID	81FR0341	Performing Org.				BYU												
PIC	UT02.401	Contract No.				03-9153												
Project Mgr.	Lindsey	Contract Start Date				2/15/2003												
Princ. Inv.	Saito	Contract End Date				2/15/2005												
FISCAL																		
Contract Amt.	\$83,000	Contract Cost to Complete				\$32,950												
Contract Cost to Date	\$50,050	Project Cost to Complete				\$42,835												
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Evaluation Study of Advanced Signal Warning Devices																	
Fund. Source	SPR	Project Type	Traffic & Safety															
Charge ID	81FR0515	Performing Org.	BYU															
PIC	AM05.001	Contract No.	05-9046															
Project Mgr.	Lindsey	Contract Start Date	7/1/2004															
Princ. Inv.	Schultz	Contract End Date	7/1/2006															
FISCAL																		
Contract Amt.	\$30,000	Contract Cost to Complete	\$30,000															
Contract Costs to Date	\$0	Project Cost to Complete	\$39,000															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title		Evaluate Traffic and Safety Initiatives																
Fund. Source	SPR	Project Type				Traffic & Safety												
Charge ID	81FR0341	Performing Org.				BYU												
PIC	UT02.401	Contract No.				03-9153												
Project Mgr.	Lindsey	Contract Start Date				2/15/2003												
Princ. Inv.	Saito	Contract End Date				2/15/2005												
FISCAL																		
Contract Amt.	\$83,000	Contract Cost to Complete				\$32,950												
Contract Cost to Date	\$50,050	Project Cost to Complete				\$42,835												
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Evaluation Study of Advanced Signal Warning Devices																	
Fund. Source	SPR	Project Type	Traffic & Safety															
Charge ID	81FR0515	Performing Org.	BYU															
PIC	AM05.001	Contract No.	05-9046															
Project Mgr.	Lindsey	Contract Start Date	7/1/2004															
Princ. Inv.	Schultz	Contract End Date	7/1/2006															
FISCAL																		
Contract Amt.	\$30,000	Contract Cost to Complete	\$30,000															
Contract Costs to Date	\$0	Project Cost to Complete	\$39,000															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Implementation of 2002 AASHTO Design Guide																	
Fund. Source	SPR				Project Type				Design									
Charge ID	BTFR0343				Performing Org.				ERES Consultants									
PIC	UT02.204				Contract No.				03-9185									
Project Mgr.	Doug Anderson				Contract Start Date				4/1/2003									
Princ. Inv.	Darter				Contract End Date				12/31/2005									
FISCAL																		
Contract Amt.	\$148,379				Contract Cost to Complete				\$52,787									
Contract Cost to Date	\$95,592				Project Cost to Complete				\$68,623									
OBJECTIVE																		
Implement the 2002 AASHTO Pavement Design Guide at UDOT. This is the first contract in a series of initiatives to get the new guide calibrated and functioning. We believe that we are two years into a five year effort.																		
IMPLEMENTATION PLAN																		
1- Identify the lab equipment needed to conduct the required materials testing. 2- Recommend traffic data gathering plans to obtain quality vehicle class and weights. 3- Train designers on how to apply the software to obtain an accurate design with the new guide both in-house and out-of-house. 4- Use the new guide to design various flexible and rigid pavements for comparison with the existing methods. Both new construction and rehabilitation projects will be included.																		
STATUS																		
A draft of the Final Report has been written. The report contains very useful comparisons of actual performance with projected performance from the design guide. A presentation is ready for the QIC, and will be scheduled for June 2005.																		
Q																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Develop a detailed work plan	Est.																
		Act.																
2	Identify the requirements, resources, and time constraints to implement the guide into UDOT practice	Est.																
		Act.																
3	Determine the impacts to UDOT of adopting the guide	Est.																
		Act.																
4	Document the study activities and outline the implementation plan	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Vehicle Feature Extraction																	
Fund. Source	SPR	Project Type	Program Development															
Charge ID	B1FR0347	Performing Org.	USU															
PIC	AM03.004	Contract No.	04-9007															
Project Mgr.	Doug Anderson	Contract Start Date	6/1/2003															
Princ. Inv.	Cheng	Contract End Date	12/31/2004															
FISCAL																		
Contract Amt.	\$45,400	Contract Cost to Complete	\$0															
Contract Cost to Date	\$45,400	Project Cost to Complete	\$0															
OBJECTIVE																		
Count and classify vehicles utilizing TOC cameras and portable cameras mounted on bridges or poles using fuzzy logic and image recognition software.																		
IMPLEMENTATION PLAN																		
Replace the time consuming manual counts with camera and advanced software. This will improve the accuracy of the information while enhancing efficiency and safety of the counting program.																		
STATUS																		
Model is done. TOC demonstration in April.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Develop the algorithms	Est.																
		Act.																
2	Conduct testing of the TOC	Est.																
		Act.																
3	Analyze the data quality	Est.																
		Act.																
4	Install at TOC and the Planning Division	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Development of Road User Cost Evaluation Tool																		
Title																		
Fund. Source	SPR	Project Type	Program Development															
Charge ID	81FR0510	Performing Org.	BYU															
PIC	H005208H	Contract No.	04-9090															
Project Mgr.	Anderson	Contract Start Date	11/1/2003															
Princ. Inv.	Saito	Contract End Date	10/31/2005															
FISCAL																		
Contract Amt.	\$35,000	Contract Cost to Complete	\$35,000															
Contract Cost to Date	\$0	Project Cost to Complete	\$45,500															
OBJECTIVE																		
1. Evaluate state of practice of user costs estimation procedures used by other states (processes, models, assumptions). 2. Evaluate major software used for user costs estimation. 3. Develop user costs estimation procedures (\$, software considering travel time variability). 4. Prepare guidelines for implementing the developed user costs estimation procedures (How much do we weigh user-costs? 5. Develop policy statement (draft)																		
IMPLEMENTATION PLAN																		
1. Develop consistent estimation of user costs. 2. Standardized user cost estimation procedures with its tables, nomographs and spreadsheets. 3. Training and distribution of software.																		
STATUS																		
Underway. This tool will be used for corridor level user impact analysis. Within the User Impact Planning policy this method will be used on Level 2 and Level 3 projects. These are generally rural routes where bypass routes do not exist. The model has been shown to be more accurate in these areas. (Level 1 projects are best evaluated with a system model which considers bypass routes.) The tool will be used in-house by project managers and other UDOT personnel.																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Literature search	Est.																
		Act.																
2	Survey state of the practice	Est.																
		Act.																
3	Evaluate software capabilities of other states	Est.																
		Act.																
4	Develop UDOT's user costs evaluation procedure	Est.																
		Act.																
5	Prepare case studies	Est.																
		Act.																
6	Develop guidelines for selecting an appropriate procedure and draft policy	Est.																
		Act.																
7	Prepare final report	Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Utah Long Term Pavement Performance Program (LTPP) for Superpave																	
Fund. Source	Federal	Project Type																
Charge ID		Performing Org.																
PIC		Contract No.																
Project Mgr.	Doug Anderson	Contract Start Date																
Princ. Inv.		Contract End Date																
FISCAL																		
Contract Amt.	\$50,000	Contract Cost to Complete		\$50,000														
Contract Costs to Date	\$0	Project Cost to Complete		\$65,000														
OBJECTIVE																		
<p>UDOT lacks the data to validate current Superpave construction practices, how these mixes relate to pavement management models, and the data to validate materials performance models. This project will evaluate the performance of the early Superpave sections to determine these aspects.</p>																		
IMPLEMENTATION PLAN																		
<p>With the performance data in hand UDOT experts will be able to determine the benefit/cost of Superpave in Utah. We will know if improvements are needed or if we are currently receiving the value from these mixes.</p>																		
STATUS																		
<p>New project. A detailed work plan has been submitted by the U of U for review. This project is part of our "Materials Research Program". A super TAC will provide oversight on this project and the others in the program. All Region Materials Engineers and Region Pavement Management Engineers will serve on the TAC</p>																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Delineate anticipated applications of data	Est.																
		Act.																
2	Define study parameters	Est.																
		Act.																
3	Identify Superpave pavement sections to monitor	Est.																
		Act.																
4	Establish data collection protocols and instrumentation for obtaining materials, traffic, environmental, and other relevant information	Est.																
		Act.																
5	Design and construction of retrievable database for storage and summary of collected data.	Est.																
		Act.																
6	Estimate the benefit/cost for Superpave mixes in Utah.	Est.																
		Act.																
7	Recommend improvements to UDOT's mix design process	Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL			
Title	SMA Paving Mechanistic Properties		
Fund. Source	Federal	Project Type	
Charge ID		Performing Org.	
PIC		Contract No.	
Project Mgr.	Doug Anderson	Contract Start Date	
Princ. Inv.		Contract End Date	

FISCAL			
Contract Amnt.	\$100,000	Contract Cost to Complete	\$100,000
Contract Costs to Date	\$0	Project Cost to Complete	\$130,000

OBJECTIVE

With the growing use of Stone Matrix Asphalt pavement (SMA) it's mechanistic design properties: resilient modulus, dynamic modulus, flexural strength and cold weather cracking susceptibility, need to be known to full benefit of its contribution to the paving system. The information to be gathered/evaluated would be resilient modulus and dynamic modulus of SMA mixes used in Utah. Additional test to be run on selected mixes to get the cold weather and fatigue and other information i.e. Bending beam TSRT etc. These tests could be run at UNR or other Superpave center throughout the country.

IMPLEMENTATION PLAN

Better understanding of the SMA design parameters will allow the pavement designer to optimize the use of SMA in pavement design and realize cost savings in the overall pavement system. 1. Interim reports to indicate current experience and best to date design assumptions for modulus and other design inputs. 2. Final report to summarize data and provide guidelines for SMA design and use. 3. Materials Library data values 4. SPT FOP

STATUS

New project. A detailed work plan is being drafted. This project is part of our "Materials Research Program". A super TAC will provide oversight on this project and the others in the program. All Region Materials Engineers and Region Pavement Management Engineers will serve on the TAC.

TASK PROGRESS TABLE

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Materials Characterization for the Mechanistic/Empirical Pavement Design Guide																	
Fund. Source	Federal	Project Type																
Charge ID		Performing Org.		ERES Consulting														
PIC		Contract No.																
Project Mgr.	Doug Anderson	Contract Start Date																
Princ. Inv.	Darter/VonQuintas	Contract End Date																
FISCAL																		
Contract Amt.	\$150,000	Contract Cost to Complete		\$150,000														
Contract Costs to Date	\$0	Project Cost to Complete		\$195,000														
OBJECTIVE																		
Determine necessary material properties required for input into the new Mechanistic/Empirical Pavement Design Guide for Utah conditions. Populate the Materials Library as data becomes available. Continue to implement the new guide into UDOT's practices.																		
IMPLEMENTATION PLAN																		
Modify the laboratory testing, traffic data gathering, environmental inputs, and various design traffic inputs as necessary. Train all users and data suppliers.																		
STATUS																		
New project. This is the second of a series of projects to implement the new guide. A two-year detailed work plan is being prepared for review.																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Determine equipment needs	Est.																
		Act.																
2	Review current equipment evaluation process	Est.																
		Act.																
3	Purchase necessary equipment	Est.																
		Act.																
4	Determine necessary properties of material to be used for AASHTO 2002 design guide	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL

Title	Full-Depth Recycling and Stabilization of Pavement Base Layers		
Fund. Source	FHWA	Project Type	
Charge ID		Performing Org.	BYU
PIC		Contract No.	
Project Mgr.	Doug Anderson	Contract Start Date	
Princ. Inv.	Dr. Spenser Guthrie	Contract End Date	

FISCAL

Contract Amt.	\$100,000 pending	Contract Cost to Complete	#VALUE!
Contract Costs to Date	\$0	Project Cost to Complete	#VALUE!

OBJECTIVE

The use of full-depth recycling (FDR) for reconstructing deteriorated asphalt pavements is advantageous from engineering, environmental, and economics perspectives. Last year UDOT utilized the FDR process in conjunction with cement stabilization to reconstruct Interstate 84 near Morgan. The project raised several questions about the design, construction, and performance of recycled, cement-stabilized layers. For example, what is the maximum permissible ratio of reclaimed asphalt pavement (RAP) to base? How is the optimum stabilizer type and content selected? How does one know when to open the stabilized layer to traffic? How does one quantify the benefit of stabilization with respect to both strength and durability? Research is needed to address these questions.

IMPLEMENTATION PLAN

UDOT engineers will use the data and specifications for designing and constructing high-quality, recycled, stabilized pavements.

STATUS

New Project. A detailed work plan is being drafted. This project is part of our "Materials Research Program". A super TAC will provide oversight on this project and the others in the program. All Region Materials Engineers and Region Pavement Management Engineers will serve on the TAC.

TASK PROGRESS TABLE

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL			
Title	Rapidmapper New Initiative		
Fund. Source	SPR	Project Type	Utility
Charge ID	81SR0516	Performing Org.	UDOT
PIC		Contract No.	N/A
Project Mgr.	Hsiao	Contract Start Date	5/1/2005
Princ. Inv.	Sean Fernandez	Contract End Date	7/31/2005
FISCAL			
Contract Amt.	N/A	Contract Cost to Complete	N/A
Contract Costs to Date	\$15,000	Project Cost to Complete	\$15,000
OBJECTIVE			

Evaluate RappidMapper technique and compare the results with traditional survey method. Possible application to railroad crossing with SR-201.

IMPLEMENTATION PLAN

If the results is acceptable, Research will promote the product to all future survey activity when it is feasible

STATUS

Field work has started. FHWA interested in using this to record historic buildings.

TASK PROGRESS TABLE

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Monitoring Spliced Girders, Deck Panel Joints & FRP Retrofit																	
Fund. Source	SPR	Project Type								Pavements, Materials								
Charge ID	81FR0514	Performing Org.								University of Utah								
PIC	UT03.503	Contract No.								04-9129								
Project Mgr.	Hsiao	Contract Start Date								3/1/2004								
Princ. Inv.	Pantelides	Contract End Date								6/30/2006								
FISCAL																		
Contract Amt.	\$25,000	Contract Cost to Complete								\$25,000								
Contract Cost to Date	\$0	Project Cost to Complete								\$32,500								
OBJECTIVE																		
1. Performance of tendon losses, weep, shrinkage, splice diaphragm performance, and deck panel joints. 2. The FRP retrofit will study environmental effects on FRP composites including temperature, corrosion, humidity and aging.																		
IMPLEMENTATION PLAN																		
1. No additional resources required since automated data acquisition is in place. 2. Continue data acquisition, destructive testing including strength and chemical tests. 3. Analyze data, compare results to design procedures.																		
STATUS																		
Computer is currently gathering data.																		
TASK PROGRESS TABLE																		
NO.	TASK		2004				2005				2006				2007			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Collect data from 4500 South/I-15 and State Street/I-80 bridges.	Est.																
		Act.																
2	Compare results with AASHTO and conspire software for 4500 South	Est.																
		Act.																
3	Evaluate reduction factor for environment for FRP design for State Street.	Est.																
		Act.																
4	Perform destructive tests for strength and compare with design values for State Street.	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																						
Preventive Deck Joint and Surface Treatment Strategies																						
Title	SPR				Project Type				Structures													
Fund. Source	81FR0336				Performing Org.				BYU													
Charge ID	AMD4.001				Contract No.				04-9081													
PIC	Hsiao				Contract Start Date				10/10/2003													
Project Mgr.	Guthrie				Contract End Date				8/31/2005													
Princ. Inv.																						
FISCAL																						
Contract Amt.	\$79,815				Contract Cost to Complete				\$74,815													
Contract Cost to Date	\$5,000				Project Cost to Complete				\$97,260													
OBJECTIVE																						
Identify and document the state-of-the-art in deck joint and surface treatment strategies																						
IMPLEMENTATION PLAN																						
1. This research is requested by Dave Eixenberger. The implementation chance is really good. 2. The final result will present to Dave and Boyd Wheeler's groups. 3. Quarterly meetings with Dave Eixenberger and Boyd Wheeler offering implementation assistance.																						
STATUS																						
Maybe a scan tour overlapped with Bridge Deck Strategy. "Stay-in-Place Deck Forms" has been added.																						
TASK PROGRESS TABLE																						
NO.	TASK		2002				2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Round table	Est.																				
		Act.																				
2	Literature Review	Est.																				
		Act.																				
3	Review of previous UDOT research	Est.																				
		Act.																				
4	DOT survey	Est.																				
		Act.																				
5	Identification of projects	Est.																				
		Act.																				
6	Field Evaluations	Est.																				
		Act.																				
7		Est.																				
		Act.																				
8		Est.																				
		Act.																				
9		Est.																				
		Act.																				
10		Est.																				
		Act.																				

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title		Bridge Deck Strategy																
Fund. Source	SPR	Project Type				Structures												
Charge ID	81FR0210	Performing Org.				BYU												
PIC	UT01.504	Contract No.				03-9192												
Project Mgr.	Hsiao	Contract Start Date				4/4/2003												
Princ. Inv.	Guthrie	Contract End Date				5/31/2005												
FISCAL																		
Contract Amt.	\$45,362	Contract Cost to Complete				\$18,909												
Contract Cost to Date	\$26,453	Project Cost to Complete				\$24,582												
OBJECTIVE																		
Develop a protocol in the form of a manual of practice for determining whether a deck should be rehabilitated or replaced.																		
IMPLEMENTATION PLAN																		
1. Structures, Dave Nazere is ready to use this manual. 2. Present the manual at Nazere's staff meeting and have question and answer time for his staff. 3. Review the manual with Nazere quarterly after it is finished. 4. Base on the input from Nazere's group, modify the manual as needed.																		
STATUS																		
Completed. Included scan tour and a manual of practice.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Roundtable with industry experts	Est.																
		Act.																
2	Conduct literature review	Est.																
		Act.																
3	Conduct Survey	Est.																
		Act.																
4	Protocol Development	Est.																
		Act.																
5	Field Demonstration	Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Scour Countermeasure Study Phase I																	
Fund. Source	SPR	Project Type	Hydraulics															
Charge ID	B1FR0142	Performing Org.	BYU															
PIC	UT00.306	Contract No.	04-9001															
Project Mgr.	Hsiao	Contract Start Date	5/19/2003															
Princ. Inv.	Zundel	Contract End Date	5/31/2007															
FISCAL																		
Contract Amt.	\$34,160	Contract Cost to Complete	\$10,114															
Contract Cost to Date	\$24,046	Project Cost to Complete	\$13,148															
OBJECTIVE																		
1. Initiate the specs for the application of Rosgen and Rosgen type scour countermeasures. 2. Evaluate the performance of Rosgen like structures in typical mountain stream reaches. 3. Verify that Rosgen like countermeasures can be simulated using numerical modeling by apply the Surface water Modeling System software package.																		
IMPLEMENTATION PLAN																		
Conduct quarterly TAC progress meeting. Hydraulic is ready to implement as soon as the result is obtained.																		
STATUS																		
Completed . Hydraulics now has a tool for surface water models scour counter measures.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Review current Rosgen practice	Est.																
		Act.																
2	Select existing installations	Est.																
		Act.																
3	Construct numerical models in SMS	Est.																
		Act.																
4	a. Select criteria; b Design specs and guidelines	Est.																
		Act.																
5	Develop draft recommendations	Est.																
		Act.																
6	Submit a complete report	Est.																
		Act.																
7	(Possible future tasks pending Alaska's involvement decision. Possibly 2nd quarter of 2006.)	Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

STATE FUNDED STUDIES

THIS PAGE LEFT BLANK INTENTIONALLY

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Effectiveness of HOV Lanes, Ph. 3 - MPC FY05																	
Fund. Source	State	Project Type	Traffic & Safety															
Charge ID		Performing Org.	University of Utah															
PIC	MPC05.002	Contract No.	05-9116															
Project Mgr.	Lindsey	Contract Start Date	11/1/2004															
Princ. Inv.	Martin	Contract End Date	12/31/2005															
FISCAL																		
Contract Amt.	\$100,000	Contract Cost to Complete	\$100,000															
Contract Cost to Date	\$0	Project Cost to Complete	\$130,000															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Advanced Traveller Information Systems ATIS - MPC FY05																	
Fund. Source	State	Project Type	Traffic & Safety															
Charge ID	RDS050BH	Performing Org.	University of Utah															
PIC	MPC05.003	Contract No.	05-9116															
Project Mgr.	Lindsey	Contract Start Date	11/1/2004															
Princ. Inv.	Martin	Contract End Date	12/31/2005															
FISCAL																		
Contract Amt.	\$100,000	Contract Cost to Complete	\$100,000															
Contract Cost to Date	\$0	Project Cost to Complete	\$130,000															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Utah Intersection Safety - MPC FY05																	
Fund. Source	State	Project Type	Traffic & Safety															
Charge ID	81SR0510	Performing Org.	University of Utah															
PIC	MPC05.004	Contract No.	05-9116															
Project Mgr.	Lindsey	Contract Start Date	11/1/2004															
Princ. Inv.	Martin	Contract End Date	12/31/2005															
FISCAL																		
Contract Amt.	\$100,000	Contract Cost to Complete	\$100,000															
Contract Cost to Date	\$0	Project Cost to Complete	\$130,000															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Smart PDA-Software Development																	
Fund. Source	RDS0408H	Project Type	Pavement															
Charge ID	81SR0359	Performing Org.	Utah State University															
PIC	UT02.403A	Contract No.	04-9039															
Project Mgr.	Anderson	Contract Start Date	5/1/2003															
Princ. Inv.	Cheng	Contract End Date	12/31/2004															
FISCAL																		
Contract Amt.	\$85,650	Contract Cost to Complete	\$21,516															
Contract Cost to Date	\$64,134	Project Cost to Complete	\$27,971															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Smart PDA Van Instrumentation																	
Fund. Source	RDS0408H	Project Type		Pavement														
Charge ID	81SR0360	Performing Org.		Samsung														
PIC	UT02.403B	Contract No.		03-9189														
Project Mgr.	Anderson	Contract Start Date		4/1/2003														
Princ. Inv.	Dennis	Contract End Date		12/31/2004														
FISCAL																		
Contract Amt.	\$39,335	Contract Cost to Complete		\$10,500														
Contract Cost to Date	\$28,835	Project Cost to Complete		\$13,650														
OBJECTIVE																		
Conduct pavement distress surveys on the fly at highway speeds. This will improve the efficiency and safety of the operation. The van will allow a 100% sample in the outside lane; an improvement over the 10% sample. The data gathered will also be objective data as opposed to the subjective data now gathered by region staff.																		
IMPLEMENTATION PLAN																		
1- Test the van this winter for accuracy and repeatability. 2- Complete software enhancements where needed. 3- Begin surveying the highway system this summer. 4- Conduct a full analysis of the gathered system-wide data for accuracy.																		
STATUS																		
Underway. The system is in the calibration stage. A new camera has been purchased and will be installed by June. We plan to evaluate 200 to 400 miles of pavement this summer. The accuracy, repeatability and reliability of the system will be evaluated. Minor modifications will be completed as needed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Install the camera, computer, and software in the van	Est.																
		Act.																
2	Test the van in the field	Est.																
		Act.																
3	Make modifications	Est.																
		Act.																
4	Monitor the van during the surveying	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Safety Benefits of UDOT Highway Program (aka) Animal Vehicle Accident Analysis (aka) Data Mining Program for Deer Fence Safety Analysis and Domestic Animal Safety Analysis																	
Fund. Source	State	Project Type				Safety												
Charge ID	81SR0362	Performing Org.				University of Utah												
PIC	AM03.003	Contract No.				03-9178												
Project Mgr.	Anderson	Contract Start Date				4/1/2003												
Princ. Inv.	Perrin	Contract End Date				7/1/2005												
FISCAL																		
Contract Amt.	\$69,290	Contract Cost to Complete				\$36,300												
Contract Cost to Date	\$32,990	Project Cost to Complete				\$47,190												
OBJECTIVE																		
The safety benefits of various types of STIP projects were estimated, including reconstruction, rehabilitation, safety spot improvements, etc.																		
IMPLEMENTATION PLAN																		
1- Twenty-nine wild animal and eight domestic animal hot spots were identified. 2- Three presentation have been given to promote the need to correct these problems. 3- Region personnel, Central Maintenance, and Traffic & Safety personnel have been involved in the initiative to recommend strategies for correction. 4- Funding will be obtained where possible to correct these problems.																		
STATUS																		
Underway. A report has been written describing the safety benefits. Additional safety improvement, spot improvements will be added to the analysis to give a better measure of the benefits of those projects.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Identify additional spot improvement projects	Est.																
		Act.																
2	Conduct the analysis and revise the report.	Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Smart PDA-Software Development																	
Fund. Source	RDS0408H	Project Type	Pavement															
Charge ID	81SR0359	Performing Org.	Utah State University															
PIC	UT02.403A	Contract No.	04-9039															
Project Mgr.	Anderson	Contract Start Date	5/1/2003															
Princ. Inv.	Cheng	Contract End Date	12/31/2004															
FISCAL																		
Contract Amt.	\$85,650	Contract Cost to Complete	\$21,516															
Contract Cost to Date	\$64,134	Project Cost to Complete	\$27,971															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title		Smart PDA-Van Instrumentation																
Fund. Source		RDS0408H				Project Type				Pavement								
Charge ID		81SR0360				Performing Org.				Samsung								
PIC		UT02.403B				Contract No.				03-9189								
Project Mgr.		Anderson				Contract Start Date				4/1/2003								
Princ. Inv.		Dennis				Contract End Date				12/31/2004								
FISCAL																		
Contract Amt.		\$39,335				Contract Cost to Complete				\$10,500								
Contract Cost to Date		\$28,835				Project Cost to Complete				\$13,650								
OBJECTIVE																		
Conduct pavement distress surveys on the fly at highway speeds. This will improve the efficiency and safety of the operation. The van will allow a 100% sample in the outside lane; an improvement over the 10% sample. The data gathered will also be objective data as opposed to the subjective data now gathered by region staff.																		
IMPLEMENTATION PLAN																		
1- Test the van this winter for accuracy and repeatability. 2- Complete software enhancements where needed. 3- Begin surveying the highway system this summer. 4- Conduct a full analysis of the gathered system-wide data for accuracy.																		
STATUS																		
Underway. The system is in the calibration stage. A new camera has been purchased and will be installed by June. We plan to evaluate 200 to 400 miles of pavement this summer. The accuracy, repeatability and reliability of the system will be evaluated. Minor modifications will be completed as needed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Install the camera, computer, and software in the van	Est.																
		Act.																
2	Test the van in the field	Est.																
		Act.																
3	Make modifications	Est.																
		Act.																
4	Monitor the van during the surveying	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Safety Benefits of UDOT Highway Program (aka) Animal Vehicle Accident Analysis (aka) Data Mining Program for Deer Fence Safety Analysis and Domestic Animal Safety Analysis																	
Fund. Source	State	Project Type	Safety															
Charge ID	B1SR0362	Performing Org.	University of Utah															
PIC	AM03.003	Contract No.	03-9178															
Project Mgr.	Anderson	Contract Start Date	4/1/2003															
Princ. Inv.	Perrin	Contract End Date	7/1/2005															
FISCAL																		
Contract Amt.	\$69,290	Contract Cost to Complete	\$36,300															
Contract Cost to Date	\$32,990	Project Cost to Complete	\$47,190															
OBJECTIVE																		
The safety benefits of various types of STIP projects were estimated, including reconstruction, rehabilitation, safety spot improvements, etc.																		
IMPLEMENTATION PLAN																		
1- Twenty-nine wild animal and eight domestic animal hot spots were identified. 2- Three presentation have been given to promote the need to correct these problems. 3- Region personnel, Central Maintenance, and Traffic & Safety personnel have been involved in the initiative to recommend strategies for correction. 4- Funding will be obtained where possilbe to correct these problems.																		
STATUS																		
Underway. A report has been written describing the safety benefits. Additional safety improvement, spot improvements will be added to the analysis to give a better measure of the benefits of those projects.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Identify additional spot improvement projects	Est.																
		Act.																
2	Conduct the analysis and revise the report.	Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Preservation Seals																	
Fund. Source	State	Project Type	Pavement, Materials															
Charge ID	81D00033	Performing Org.	University of Utah															
PIC	UT95.102	Contract No.	03-9053															
Project Mgr.	Anderson	Contract Start Date	9/1/2002															
Princ. Inv.	Romero	Contract End Date	9/1/2005															
FISCAL																		
Contract Amt.	\$25,311	Contract Cost to Complete	\$0															
Contract Cost to Date	\$25,311	Project Cost to Complete	\$0															
OBJECTIVE																		
Measure the practical life of open graded surface courses and chip seals. Determine how other agencies in the country use preservation seals.																		
IMPLEMENTATION PLAN																		
1- Recommend strategies, budgets, and policies related to preservation seals. 2- Improved designs and materials will be outlined to give longer lasting and better performing seals. 3- Changes in policies concerning both OGSCs and chip seals will be recommended.																		
STATUS																		
Underway. The report is being written. The draft is being reviewed and the recommendation under consideration. Changes in UDOT's seal coat program will be recommended.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Present findings and recommendations	Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Skid Deficiency Process (Skid Index Trigger Values)																	
Fund. Source		Project Type																
Charge ID		Performing Org.	UDOT QIT															
PIC		Contract No.																
Project Mgr.	Doug Anderson	Contract Start Date																
Princ. Inv.		Contract End Date																
FISCAL																		
Contract Amt.	\$10,000	Contract Cost to Complete	\$10,000															
Contract Costs to Date	\$0	Project Cost to Complete	\$13,000															
OBJECTIVE																		
Identify Trigger values for pavement sections with inadequate skid index values, and implement a process to determine the best strategy for correcting the problem. Other factors will be considered including skid history, other pavement condition deficiencies, crash history, wet weather crashes, AADT, geometrics, the cause of the problem, and the urgency.																		
IMPLEMENTATION PLAN																		
Form a QIT to represent pavement Condition Surveys, Pavement Management, Safety, Maintenance, and Asset Management. Draft a process for approval by upper management.																		
STATUS																		
New project. The QIT has met, and agreed on a basic plan to proceed. Some information will be acquired from the data mining project "Slippery Pavement Safety Study". The basics of the process have been outlined. Details will follow.																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Form a QIT	Est.																
		Act.																
2	Draft a process	Est.																
		Act.																
3	Implement into UDOT practice	Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Hydraulic Discharge Calcs Ph. 2 (Frequency)																	
Fund. Source	State	Project Type	Hydraulics															
Charge ID	B1SH0350	Performing Org.	Utah State University															
Project No.	UT02.301A	Contract No.	04-9123															
Project Mgr.	Hsiao	Contract Start Date	2/1/2004															
Princ. Inv.	Grenney	Contract End Date	2/28/2005															
FISCAL																		
Contract Amt.	\$20,498	Contract Cost to Complete	\$0															
Contract Cost to Date	\$20,498	Project Cost to Complete	\$0															
OBJECTIVE																		
Investigate the accuracy of the Intensity-Duration-Frequency (IDF) curves. Compare IDF for Utah derived from several sources. Compare current data with data previously used for design. Evaluate IDF for the same elev but onopposite sides of a mountain ridge.																		
IMPLEMENTATION PLAN																		
Developed IDF curve. Hydraulics is using the data.																		
STATUS																		
Complete																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Compare NOAA website with traditional IDF design data for Salt Lake, Hill AFB, Ogden and Modena areas	Est.																
		Act.																
2	Select at least 3 locations within the state where it is known that there is a pronounced orographic effect and test with NOAA info.	Est.																
		Act.																
3	Identify sources for the other types of data commonly used for estimation peak flows including precipitation, vegetation and soils.	Est.																
		Act.																
4	Downloading the data into the WMS program	Est.																
		Act.																
5	Provide CD containing the most current digital data.	Est.																
		Act.																
6	Compile the written results of the above deliverables in to a final report.	Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title		Crash Data Delivery Using GIS Ph. 2																
Fund. Source	State	Project Type	Traffic and Safety															
Charge ID	81SR0341	Performing Org.	IWORK															
PIC	UT01.402	Contract No.	03-9041															
Project Mgr.	Doug Anderson	Contract Start Date	9/1/2002															
Princ. Inv.	Perrett	Contract End Date	12/31/2004															
FISCAL																		
Contract Amt.	\$7,950	Contract Cost to Complete	\$999															
Contract Cost to Date	\$6,951	Project Cost to Complete	\$1,299															
OBJECTIVE																		
Deliver crash information through a web application for use by UDOT decision-makers.																		
IMPLEMENTATION PLAN																		
1- Train end users on how to conduct queries against the database. Fourteen training sessions have been held and numerous one on one training has been conducted. 2- Illustrate through presentations how the tool can be used to identify hot spots, make safety related decisions to reduce the problem, and measure the results over time. 3- The Data Mining Program will continue to use this tool to study specific safety issues.																		
STATUS																		
Implementation phase—update data almarac. Contract is completed. Further work possibly via pool contract as needed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Complete Implementation	Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Discharge Recalculations Ph. 2 (Canyons)																		
Title																		
Fund. Source	State	Project Type	Hydraulics															
Charge ID	81SR0441	Performing Org.	University of Utah															
PIC	UT02 301B	Contract No.	04-9029															
Project Mgr.	Hsiao	Contract Start Date	8/1/2003															
Princ. Inv.	Perica	Contract End Date	9/1/2004															
FISCAL																		
Contract Amt.	\$42,500	Contract Cost to Complete	\$0															
Contract Cost to Date	\$42,500	Project Cost to Complete	\$0															
OBJECTIVE																		
Estimate reliable design flood magnitudes for Weber River basin in Utah.																		
IMPLEMENTATION PLAN																		
Hydraulic group is ready to implement as soon as the research is completed.																		
STATUS																		
Developed new equations and hydraulics is using them.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Select study area and perform quality control of the streamflow data.	Est.																
		Act.																
2	Estimate regional skew.	Est.																
		Act.																
3	Perform flood frequency analysis	Est.																
		Act.																
4	Calculate watershed characteristics that will be investigated as possible predictors of T-year flows.	Est.																
		Act.																
5	Develop regional flood frequency equations	Est.																
		Act.																
6	Prepare the final report.	Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Utah Rockfall Hazard Rating System and Maintenance Management Program																	
Fund. Source	State	Project Type	Maintenance, Geotechnical															
Charge ID	81SR0291	Performing Org.	Utah State University															
PIC	UT97.542	Contract No.	04-9072															
Project Mgr.	Leonard/Farnsworth	Contract Start Date	1-May-01															
Princ. Inv.	Pack	Contract End Date	31-May-04															
FISCAL																		
Contract Amt.	\$40,000	Contract Cost to Complete	\$12,500															
Contract Cost to Date	\$27,500	Est. Current FY Cost	\$0															
OBJECTIVE																		
Establish and implement a Utah Rockfall Hazard Rating system along UDOT roadways, including the development of a database with a complete compilation of rockfall locations and parameters. Establish a system of prioritization to identify appropriate locations for mitigation efforts for rockfall slopes, and create a maintenance management program to ensure that prioritized rockfall locations receive appropriate attention and mitigation efforts.																		
IMPLEMENTATION PLAN																		
Based on the prioritized rockfall sites, begin to plan mitigation and maintenance efforts for the highest priority sites.																		
STATUS																		
Phase 1 Complete. Report Published: UT-03.01 "Utah Rockfall Hazards Inventory - Phase I", Apr 02. Phase 2a Complete. Phase 2b underway. Database complete. Resolving final details of the prioritization algorithm. Contract extension will be needed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Phase II - Part 2: Complete the Utah Rockfall Inventory (189 sites)	Est.																
		Act.																
2	Finalize the Utah Rockfall Hazard Rating System	Est.																
		Act.																
3	Prepare Final ArcView GIS Database	Est.																
		Act.																
4	Final Report	Est.																
		Act.																
5	Training Session and Final TAC Meeting	Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Experimental Determination of Dynamic Characteristics of New Bridges (Forced Vibration, Phase 3)																	
Fund. Source	State	Project Type	Structures															
Charge ID	B1S15302	Performing Org.	Utah State University															
PIC	TB00.302	Contract No.	04-B150															
Project Mgr.	Leonard	Contract Start Date	1-Jan-04															
Princ. Inv.	Halling	Contract End Date	30-May-05															
FISCAL																		
Contract Amt.	\$170,500	Contract Cost to Complete	\$35,500															
Contract Cost to Date	\$135,000	Project Cost to Complete	\$46,150															
OBJECTIVE																		
Evaluate the dynamic properties of several existing bridge structures to secure an adequate characterization of these bridges, and to use this information to compare the design models with the actual field data to see if the bridges behave as modeled. Archive the detailed dynamic signature of new structures for use in the investigation of future deterioration or seismic damage of the structures.																		
IMPLEMENTATION PLAN																		
This project is one additional step toward the use of modal analysis as a non-destructive evaluation technique for post-seismic damage and long term deterioration of bridge structures. The data obtained from this study will be used to verify and develop this technique further, and provide a valuable database of information for subsequent studies.																		
STATUS																		
Testing and analysis complete. Draft report being prepared.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Bridge 1 (C-846): Field Instrumentation and Testing	Est.																
		Act.																
2	Bridge 1 (C-846): Data Analysis and FEM Modeling	Est.																
		Act.																
3	Bridge 1 (C-846): Report Preparation	Est.																
		Act.																
4	Bridge 2 (C-814 Vine Street): Field Instrumentation and testing.	Est.																
		Act.																
5	Bridge 2 (C-814 Vine Street): Data Analysis and FEM Modeling	Est.																
		Act.																
6	Bridge 2 (C-814 Vine Street): Report Preparation	Est.																
		Act.																
7	Bridge 3: (NB Cherry Hill Off Ramp): Field Instrumentation and Testing	Est.																
		Act.																
8	Bridge 3: (NB Cherry Hill Off Ramp): Data Analysis and FEM Modeling	Est.																
		Act.																
9	Bridge 3: (NB Cherry Hill Off Ramp): Report Preparation	Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Effectiveness of HOV Lanes, Ph. 3 - MPC FY05																	
Fund. Source	State	Project Type	Traffic & Safety															
Charge ID		Performing Org.	University of Utah															
PIC	MPC05.002	Contract No.	05-9116															
Project Mgr.	Lindsey	Contract Start Date	11/1/2004															
Princ. Inv.	Martin	Contract End Date	12/31/2005															
FISCAL																		
Contract Amt.	\$100,000	Contract Cost to Complete	\$100,000															
Contract Cost to Date	\$0	Project Cost to Complete	\$130,000															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
Project on schedule																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Meet with TAC define scope	Est.																
		Act.																
2	Design and ATCS evaluation	Est.																
		Act.																
3	approval of detail evaluation design	Est.																
		Act.																
4	Collect data	Est.																
		Act.																
5	Analyse data	Est.																
		Act.																
6	Meet with TAC and present finding	Est.																
		Act.																
7	Deliver results	Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Adaptive Signal Control Implementation & Evaluation - MPC FY05																	
Fund. Source	State	Project Type	Traffic & Safety															
Charge ID	81SR0510	Performing Org.	University of Utah															
PIC	MPC05.001	Contract No.	05-9116															
Project Mgr.	Lindsey	Contract Start Date	11/1/2004															
Princ. Inv.	Martin	Contract End Date	12/31/2005															
FISCAL																		
Contract Amt.	\$100,000	Contract Cost to Complete	\$100,000															
Contract Cost to Date	\$0	Project Cost to Complete	\$130,000															
OBJECTIVE																		
IMPLEMENTATION PLAN																		
STATUS																		
The project is behind schedule due to the device being hit which caused the project to have more data collection time																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Meet with Tac define criteria	Est.																
		Act.																
2	Design an ATCS evaluation.	Est.																
		Act.																
3	Detail evaluation of design	Est.																
		Act.																
4	Collect data before the ATCS	Est.																
		Act.																
5	Turn on the system	Est.																
		Act.																
6	Collect data after the ATCS	Est.																
		Act.																
7	Observe and survey the T2	Est.																
		Act.																
8	Analyze data and produce results	Est.																
		Act.																
9	Meet with TAC and present findings	Est.																
		Act.																
10	Deliver report	Est.																
		Act.																

**I-15 TEST BED FUNDED STUDIES
PHASES 1-4**

THIS PAGE LEFT BLANK INTENTIONALLY

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Long term structural monitoring of post-tensioned spliced girders and deck joints																	
Fund. Source	I-15 Test Bed	Project Type	Structures															
Charge ID	81F155303	Performing Org.	University of Utah															
PIC	TB00.303	Contract No.	02-9166															
Project Mgr.	Hsiao	Contract Start Date	8/1/2001															
Princ. Inv.	Pantelides	Contract End Date	6/30/2006															
FISCAL																		
Contract Amt.	\$194,500	Contract Cost to Complete	\$0															
Contract Costs to Date	\$194,500	Project Cost to Complete	\$0															
OBJECTIVE																		
<p>The primary objective of the research is to determine the long term performance of spliced prestressed girders used in R/C concrete bridges. This includes the following sub-subjectives: a) Compare the prestress losses, deflections, and creep parameters obtained from field measurements of the spliced precast girders. b) Compare these field measurement to finite element computer programs for vertical load, fatigue load, thermal load and tendon losses. c) Develop guidelines for design modifications and improvements for the future design and installation of the spliced girders, such as curing time required before post tensioning, etc.</p>																		
IMPLEMENTATION PLAN																		
<p>This is information getting research, and the</p>																		
STATUS																		
<p>Final report is done and the project is completed.</p>																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Evaluate concrete, steel, and post tensioning strand material properties.	Est.																
		Act.																
2	Install additional sensors and automatic data acquisition system.	Est.																
		Act.																
3	Collect field measurements from placed on selected girders and the deck	Est.																
		Act.																
4	Analyze all data gathered during the 21 month data collection period	Est.																
		Act.																
5	Develop analytical models designed to predict the structural and thermal behavior of the post tensioned girders both during and after construction	Est.																
		Act.																
6	Perform two truck load tests during the course of 2 years	Est.																
		Act.																
7	Develop an intrum report	Est.																
		Act.																
8	Develop a final report intended for publication	Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Evaluation of Fiber Reinforced Polymer Composite Confined Rectangular Concrete Columns																	
Fund. Source	I-15 Testbed	Project Type	Structures															
Charge ID	81F15406	Performing Org.	University of Utah															
PIC	TB01.406	Contract No.	03-9056															
Project Mgr.	Hsiao	Contract Start Date	9/3/2002															
Princ. Inv.	Pantelides	Contract End Date	8/31/2005															
FISCAL																		
Contract Amt.	\$161,924	Contract Cost to Complete	\$0															
Contract Costs to Date	\$166,000	Project Cost to Complete	\$0															
OBJECTIVE																		
Develop design guides for fiber reinforced polymer composite retrofit of rectangular concrete columns. Specific objectives will be achieved: a) Perform full scale laboratory experiments on circular, square, and rectangular columns wrapped with composites. 2) Develop an analytical model for describing the confinement provided by the FRP composite for rectangular columns wrap. 3) Develop guidelines for design of FRP jackets for rectangular columns, and techniques for using the FRP confined concrete properties in pushover analyses of retrofitted concrete bridges.																		
IMPLEMENTATION PLAN																		
This project has low value for current structures application.																		
STATUS																		
All tasks are completed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Review existing experimental results and analytical models for FRP jexketed rectangular concrete columns	Est.																
		Act.																
2	Test full scale models of circular, square, and rectangular columns wrapped with FRP composites	Est.																
		Act.																
3	Develop analytical models for FRP confined rectangular concrete columns.	Est.																
		Act.																
4	Verify the analytical FRP confined concrete model with finite element analyses.	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

THIS PAGE LEFT BLANK INTENTIONALLY

INNOVATIVE BRIDGE FUNDED STUDIES

THIS PAGE LEFT BLANK INTENTIONALLY

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Evaluate Feasibility of using MMFX rebar and HPS performance																	
Fund. Source	Innovative Bridge Fund	Project Type	Structures															
Charge ID	5075715D	Performing Org.	Utah State University															
PIC		Contract No.	Pending															
Project Mgr.	Hsiao	Contract Start Date	Pending															
Princ. Inv.	Barr	Contract End Date	Pending															
FISCAL																		
Contract Amt.	pending	Contract Cost to Complete	Pending															
Contract Costs to Date	pending	Project Cost to Complete	Pending															
OBJECTIVE																		
Evaluate MMFX rebar of its possibility to be used as UDOT standard reinforcing steel for concrete. Give recommendations to UDOT. Review high performance steel performance in design process. The advantage and disadvantage by using the full strength of the HPS ability																		
IMPLEMENTATION PLAN																		
Based on the recommendation, UDOT will determine the usage of the above material and application criteria																		
STATUS																		
Contract is in progress																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1		Est.																
		Act.																
2		Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	3760 S. and 3900 S. on I-215 Bridge Replacement by Prefabricated Elements																	
Fund. Source	Innovative Bridge	Project Type	Structures															
Charge ID	81FB0851	Performing Org.	MD ²															
PIC	IB04.001	Contract No.	04-9103															
Project Mgr.	Hsiao	Contract Start Date	1/1/2003															
Princ. Inv.	Dye	Contract End Date	7/1/2005															
FISCAL																		
Contract Amt.	\$34,800	Contract Cost to Complete	\$12,750															
Contract Cost to Date	\$22,050	Project Cost to Complete	\$16,575															
OBJECTIVE																		
Provide "lessons learned report after construction" for structures and construction engineers and technicians.																		
IMPLEMENTATION PLAN																		
1. Present "Lessons Learned Report after Construction" to the Structures and Construction engineers. 2. Present a modified report to the construction technicians. 3. Present the report to the Engineering conference. 4. Visit construction and structures engineers regularly to assure that the lessons learned have been implemented.																		
STATUS																		
The project progress is dictated by the construction schedule. It is anticipated that the Lessons Learned report will be done in July, 2005. Deliverable to Structures & Regions.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Develop the plan, task 1-3	Est.																
		Act.																
2	Collect construction documents for lessons learned report, task 4-12	Est.																
		Act.																
3	Attend TAC meetings, task 13	Est.																
		Act.																
4	Site inspection after construction, task 14	Est.																
		Act.																
5	Attend PS & E meeting, task 15	Est.																
		Act.																
6	Prepare lessons learned report after the construction, task 16-18	Est.																
		Act.																
7	Present lessons learned report after construction, task 19-21, and plant visit	Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Stainless Clad Rebar Study																	
Fund. Source	Innovative Bridge	Project Type	Structures															
Charge ID	81FB0676	Performing Org.	Earth Tech															
PIC	IB02.001	Contract No.	02-9195															
Project Mgr.	Daniel Hsiao	Contract Start Date	7/1/2001															
Princ. Inv.	Carter	Contract End Date	12/31/2006															
FISCAL																		
Contract Amt.	\$77,260	Contract Cost to Complete	\$4,920															
Contract Cost to Date	\$72,340	Project Cost to Complete	\$6,396															
OBJECTIVE																		
Assess the potential cost savings resulting from using stainless clad rebar.																		
IMPLEMENTATION PLAN																		
Will present the findings at Boyd Wheeler's staff meeting. If the finding is positive, research will help Structures in specs developing and apply the new material to other projects. Find out the cost savings to the Department.																		
STATUS																		
In progress. However, because of the stainless clad rebar manufacturer did not deliver on time for the construction season, the objective can not be reached. Since no field installation, structures will spend the remaining funds used to visit the North Carolina Plant.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Literature and phone survey	Est.																
		Act.																
2	Modifications to bridge construction bid documents	Est.																
		Act.																
3	Detailed evaluation and instrumentation plan	Est.																
		Act.																
4	Interim report	Est.																
		Act.																
5	Installation of corrosion monitoring system	Est.																
		Act.																
6	Assessment of constructability issues	Est.																
		Act.																
7	Final report	Est.																
		Act.																
8	Scanning tour	Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

POOLED FUND LEAD STATE STUDIES

THIS PAGE LEFT BLANK INTENTIONALLY

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Pavement Marking Life Cycle, Ph. 2																	
Fund. Source	SPR	Project Type	Traffic & Safety, Maintenance															
Charge ID	4001808H	Performing Org.	BC Traffic															
PIC	PL02.094	Contract No.	03-9184															
Project Mgr.	Berg	Contract Start Date	9/1/2002															
Princ. Inv.	Beck	Contract End Date	6/30/2006															
FISCAL																		
Contract Amt.	\$319,944	Contract Cost to Complete	\$265,246															
Contract Cost to Date	\$54,698	Project Cost to Complete	\$344,820															
OBJECTIVE																		
Develop life cycle curves for methylmethacrylate, thermoplastic, tape, and epoxy pavement markings based on AADT, pavement type and winter maintenance.																		
IMPLEMENTATION PLAN																		
Curves will be used to predict location specific performance of selected pavement markings that will contribute to BMP for pavement marking programs.																		
STATUS																		
First three years of data has been collected and evaluated. Data collection continues this year. Because of personnel changes with Texas Transportation Institute, data evaluation and presentation is behind schedule. The contractor is working with them to get back on schedule.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Collect 2002 Data	Est.																
		Act.																
2	Evaluate and present 2002 Data	Est.																
		Act.																
3	Collect 2003 Data	Est.																
		Act.																
4	Evaluate and present 2003 Data	Est.																
		Act.																
5	Collect 2004 Data	Est.																
		Act.																
6	Evaluate and present 2004 Data	Est.																
		Act.																
7	Collect 2005 Data	Est.																
		Act.																
8	Evaluate and present 2005 Data	Est.																
		Act.																
9	Final report and recommendations	Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	WASHTO-X																	
Fund. Source	SPR	Project Type	Technology Transfer															
Charge ID	4002108H	Performing Org.	USU															
PIC		Contract No.	'02-4302 TPF-5(017)															
Project Mgr.	Doug Anderson	Contract Start Date																
Princ. Inv.	Bolling	Contract End Date																
FISCAL																		
Contract Amt.		Contract Cost to Complete	\$0															
Contract Costs to Date	\$0	Project Cost to Complete	\$0															
OBJECTIVE																		
Conduct technology transfer sessions on technical and administrative transportation issues. Fourteen of the WASHTO States have agreed to participate and contributed funding through a pooled-fund project.																		
IMPLEMENTATION PLAN																		
1- Conduct sessions on pressing issues that are proposed by the state agencies. 2- Measure the benefits through feedback surveys. 3- The program has been proposed for continuance for another two years. The program can be maintained at a lower cost than it took to create it and role it out. 4- Present the lessons learned from the program to other regions in the country.																		
STATUS																		
Underway. A final report has been written and distributed describing the program benefits. It has been determined that 34% of the participants have changed the way they do business as a result of attending the session. More than 90% will attend another session. A second two-year program of sessions has been planned.																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Present findings from the first two years.	Est.																
		Act.																
2	Begin the second series of sessions	Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

**I-15 TEST BED FUNDED STUDIES
PHASES 1-4**

THIS PAGE LEFT BLANK INTENTIONALLY

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Non-Destructive Evaluation Method to Determine Residual Tendon Stress in Pre-Stressed Girders																	
Fund. Source	I-15 Test Bed Ph. 4	Project Type	Structures															
Charge ID	81FR0404	Performing Org.	Utah State University															
PIC	TB01.404	Contract No.	05-9040															
Project Mgr.	Leonard	Contract Start Date	1-Jun-04															
Princ. Inv.	Paul Barr	Contract End Date	30-Jun-08															
FISCAL																		
Contract Amt.	\$173,285	Contract Cost to Complete	\$138,285															
Contract Cost to Date	\$35,000	Project Cost to Complete	\$179,771															
OBJECTIVE																		
Investigate the feasibility and effectiveness of non destructively determining the residual force in tendons of pre stressed girders by isolating, but not removing, a small block on the tensile face of the girder.																		
IMPLEMENTATION PLAN																		
If the method is successful, UDOT bridge inspection and rating procedures to incorporate this new technique.																		
STATUS																		
Laboratory set-up and literature search underway. Fabrication of concrete cylinders in progress.																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Literature Search	Est.																
		Act.																
2	Laboratory Testing Preparation / Compression Testing	Est.																
		Act.																
3	Finite Element Modeling of Cylinders	Est.																
		Act.																
4 / 5	Laboratory Testing of Cylinders / Data Analysis	Est.																
		Act.																
6	Laboratory Prep for Model Beam Tests	Est.																
		Act.																
7	Finite Element Modeling of Model Pre-Stressed Beams	Est.																
		Act.																
8 / 9 / 10	Model Beam Fabrication / Testing / Data Analysis / Interim Report	Est.																
		Act.																
12	Finite Element Modeling of Girders	Est.																
		Act.																
11 / 13 / 14	Full Scale Test Preparation / Girder Testing / Data Analysis	Est.																
		Act.																
15	Final Report	Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

[illegible]

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Evaluation of Fiber Reinforced Polymer Composite Confined Rectangular Concrete Columns																	
Fund. Source	I-15 Testbed	Project Type	Structures															
Charge ID	B1F15406	Performing Org.	University of Utah															
PIC	TB01.406	Contract No.	03-9056															
Project Mgr.	Hslao	Contract Start Date	9/3/2002															
Princ. Inv.	Pantelides	Contract End Date	8/31/2005															
FISCAL																		
Contract Amt.	\$161,924	Contract Cost to Complete	\$0															
Contract Costs to Date	\$166,000	Project Cost to Complete	\$0															
OBJECTIVE																		
Develop design guides for fiber reinforced polymer composite retrofit of rectangular concrete columns. Specific objectives will be achieved: a) Perform full scale laboratory experiments on circular, square, and rectangular columns wrapped with composites. 2) Develop an analytical model for describing the confinement provided by the FRP composite for rectangular columns wrap. 3) Develop guidelines for design of FRP jackets for rectangular columns, and techniques for using the FRP confined concrete properties in pushover analyses of retrofitted concrete bridges.																		
IMPLEMENTATION PLAN																		
This project has low value for current structures application.																		
STATUS																		
All tasks are completed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Review existing experimental results and analytical models for FRP jacked rectangular concrete columns	Est.																
		Act.																
2	Test full scale models of circular, square, and rectangular columns wrapped with FRP composites	Est.																
		Act.																
3	Develop analytical models for FRP confined rectangular concrete columns.	Est.																
		Act.																
4	Verify the analytical FRP confined concrete model with finite element analyses.	Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	Long term structural monitoring of post-tensioned spliced girders and deck joints																	
Fund. Source	I-15 Test Bed	Project Type	Structures															
Charge ID	81F155303	Performing Org.	University of Utah															
PIC	TB00.303	Contract No.	02-9166															
Project Mgr.	Hsiao	Contract Start Date	8/1/2001															
Princ. Inv.	Pantelides	Contract End Date	6/30/2006															
FISCAL																		
Contract Amt.	\$194,500	Contract Cost to Complete	\$0															
Contract Costs to Date	\$194,500	Project Cost to Complete	\$0															
OBJECTIVE																		
The primary objective of the research is to determine the long term performance of spliced prestressed girders used in R/C concrete bridges. This includes the following sub-subjectives: a) Compare the prestress losses, deflections, and creep parameters obtained from field measurements of the spliced precast girders. b) Compare these field measurement to finite element computer programs for vertical load, fatigue load, thermal load and tendon losses. c) Develop guidelines for design modifications and improvements for the future design and installation of the spliced girders, such as curing time required before post tensioning, etc.																		
IMPLEMENTATION PLAN																		
This is information getting research, and the																		
STATUS																		
Final report is done and the project is completed.																		
TASK PROGRESS TABLE																		
NO.	TASK		2005				2006				2007				2008			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Evaluate concrete, steel, and post tensioning strand material properties.	Est.																
		Act.																
2	Install additional sensors and automatic data acquisition system.	Est.																
		Act.																
3	Collect field measurements from placed on selected girders and the deck	Est.																
		Act.																
4	Analyze all data gathered during the 21 month data collection period	Est.																
		Act.																
5	Develop analytical models designed to predict the structural and thermal behavior of the post tensioned girders both during and after construction	Est.																
		Act.																
6	Perform two truck load tests during the course of 2 years	Est.																
		Act.																
7	Develop an intrum report	Est.																
		Act.																
8	Develop a final report intended for publication	Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

POOLED FUND LEAD STATE STUDIES

THIS PAGE LEFT BLANK INTENTIONALLY

GENERAL																		
Title	Pavement Marking Life Cycle, Ph. 2																	
Fund. Source	SPR	Project Type	Traffic & Safety, Maintenance															
Charge ID	4001808H	Performing Org.	BC Traffic															
PIC	PL02.094	Contract No.	03-9184															
Project Mgr.	Berg	Contract Start Date	9/1/2002															
Princ. Inv.	Beck	Contract End Date	6/30/2006															
FISCAL																		
Contract Amt.	\$319,944	Contract Cost to Complete	\$265,246															
Contract Cost to Date	\$54,698	Project Cost to Complete	\$344,820															
OBJECTIVE																		
Develop life cycle curves for methylmethacrylate, thermoplastic, tape, and epoxy pavement markings based on AADT, pavement type and winter maintenance.																		
IMPLEMENTATION PLAN																		
Curves will be used to predict location specific performance of selected pavement markings that will contribute to BMP for pavement marking programs.																		
STATUS																		
First three years of data has been collected and evaluated. Data collection continues this year. Because of personnel changes with Texas Transportation Institute, data evaluation and presentation is behind schedule. The contractor is working with them to get back on schedule.																		
TASK PROGRESS TABLE																		
NO.	TASK		2002				2003				2004				2005			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Collect 2002 Data	Est.																
		Act.																
2	Evaluate and present 2002 Data	Est.																
		Act.																
3	Collect 2003 Data	Est.																
		Act.																
4	Evaluate and present 2003 Data	Est.																
		Act.																
5	Collect 2004 Data	Est.																
		Act.																
6	Evaluate and present 2004 Data	Est.																
		Act.																
7	Collect 2005 Data	Est.																
		Act.																
8	Evaluate and present 2005 Data	Est.																
		Act.																
9	Final report and recommendations	Est.																
		Act.																
10		Est.																
		Act.																

RESEARCH PROJECT STATUS SHEET

GENERAL																		
Title	WASHTO-X																	
Fund. Source	SPR	Project Type	Technology Transfer															
Charge ID	4002108H	Performing Org.	USU															
PIC		Contract No.	'02-4302 TPF-5(017)															
Project Mgr.	Doug Anderson	Contract Start Date																
Princ. Inv.	Bolling	Contract End Date																
FISCAL																		
Contract Amt.		Contract Cost to Complete	\$0															
Contract Costs to Date	\$0	Project Cost to Complete	\$0															
OBJECTIVE																		
<p>Conduct technology transfer sessions on technical and administrative transportation issues. Fourteen of the WASHTO States have agreed to participate and contributed funding through a pooled-fund project.</p>																		
IMPLEMENTATION PLAN																		
<p>1- Conduct sessions on pressing issues that are proposed by the state agencies. 2- Measure the benefits through feedback surveys. 3- The program has been proposed for continuance for another two years. The program can be maintained at a lower cost than it took to create it and role it out. 4- Present the lessons learned from the program to other regions in the country.</p>																		
STATUS																		
<p>Underway. A final report has been written and distributed describing the program benefits. It has been determined that 34% of the participants have changed the way they do business as a result of attending the session. More than 90% will attend another session. A second two-year program of sessions has been planned.</p>																		
TASK PROGRESS TABLE																		
NO.	TASK		2003				2004				2005				2006			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
1	Present findings from the first two years.	Est.																
		Act.																
2	Begin the second series of sessions	Est.																
		Act.																
3		Est.																
		Act.																
4		Est.																
		Act.																
5		Est.																
		Act.																
6		Est.																
		Act.																
7		Est.																
		Act.																
8		Est.																
		Act.																
9		Est.																
		Act.																
10		Est.																
		Act.																

APPENDIX

THIS PAGE LEFT BLANK INTENTIONALLY



U.S. Department
Of Transportation
**Federal Highway
Administration**

Utah Division
2520 West 4700 South, Ste. 9A
Salt Lake City, UT 84118-1847

June 30, 2005

File: 6020

Rukhsana Lindsey, Engineer For Research and Development
Utah Department of Transportation
4501 South 2700 West
Salt Lake City, UT 84119

SUBJECT: UDOT SFY 2006 Annual Research Division SPR Work Program

Dear Ms. Lindsey:

We have received and reviewed the SFY 2006 Research Work Program. Work may commence on the SPR-funded projects contained in the program. Other projects listed in the program are valuable for informational purposes. We greatly appreciate the consolidated approach the Research Division is now taking with regards to the work program. Please note the following important dates:

Key Dates	Actions
June 30, 2005	<ul style="list-style-type: none">▪ SFY 2006 Research Work Program is Approved▪ Work henceforth on SPR projects contained in the SFY 2005 Work Program is eligible for SPR reimbursement until the approval expires.▪ All previous work programs expire. Work continuing after August 13 in previous work programs is ineligible for reimbursement. Invoices for work completed prior to August 13 are still acceptable.
January 1, 2006	<ul style="list-style-type: none">▪ FFY 2005 work program must be closed. No charges honored thereafter.
June 1, 2006	<ul style="list-style-type: none">▪ Draft SFY 2007 Work Program should be delivered to FHWA Utah Division for review.

Any projects not contained in the SFY06 Work Program intended to begin this state fiscal year may be added to the program by amendment. Amendments may be submitted by email to the FHWA Research Program Manager for electronic approval. Amendments need to contain new "Research Project Status Sheets" and a corresponding update to the budget worksheets in the beginning of the work program.

This approval is in anticipation of future Federal funds. The Federal Government assumes no obligation to reimburse for research work beyond available funding levels.



Should you have any questions, please do not hesitate to contact me. I can be reached at 963-0078 ext. 236.

Sincerely,



Paul Mooney
Technology and Marketing Specialist

CC:

Jim McMinimee, UDOT, Project Development, Box 8380

Michelle Page, UDOT, Research, Box 8410

Frank Long, FHWA

Kelly Garner, UDOT, Comptroller, Box 3600

Steve Call, FHWA

PMOONEY:dm

