

UDOT Minimum Sampling and Testing Requirement

Revised: May 2006

02645 Precast Concrete Box Culvert

02645

Standard Specification

Related Items: N/A

Type of Construction: Precast Concrete Box Culvert

Submittals:

Quality Assurance: Fabricators must be pre-qualified by the Materials Division through the Quality Management Plan: Precast/Prestressed Concrete Structures. Select from Materials Division list of pre-qualified sources.

Assurance Frequency: N/A

Point of Acceptance: Prequalified Source

Out of Spec Action: Rejection of product and possible removal from pre-qualified source list.

Documentation/Report:

Type of Construction:

Submittals:

Quality Assurance: Test Report

Assurance Frequency: Issued by Central Lab based on tests performed prior to shipment. A test report will accompany the shipment. All pretested material will be tagged with an orange UDOT sticker.

Point of Acceptance: Fabricators Plant

Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Concrete

Submittals:

Quality Assurance: Per Section 03055 except as follows. Mix Design(Trial Batches) must be submitted and approved, by the Materials Division, each new calendar year.

Assurance Frequency: N/A

Point of Acceptance: N/A

Out of Spec Action: N/A

Documentation/Report:

*Performed or approved by Region Lab **Performed by Contractor and reviewed by Engineer

Printed 6/2/2006

Related Items: 03211 Reinforcing Steel (Epoxy Coated), 03211 Welded Steel Wire

Type of Construction:**Submittals:****Quality Assurance:** Visual Inspection**Assurance Frequency:** Each Shipment**Point of Acceptance:** Project site**Out of Spec Action:** Rejection**Documentation/Report:**