UDOT Minimum Sampling and Testing Requirement

02610 Pipe Culverts

02610

Standard Specification

Related Items: N/A

Type of Construction: Asphalt Coating

Submittals:

Quality Assurance: Test Report

Assurance Frequency: Issued by Central Lab (Asphalt/Chemistry Lab) based on tests

performed prior to shipment. A test report will be supplied prior

to shipment.

Point of Acceptance: Central Lab (Asphalt/Chemistry Lab)

Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Corrugated Pipe Culverts and Pipe Arch Culverts

Submittals:

Quality Assurance: Manufacturer's Certificate of Compliance

Assurance Frequency: Each Shipment
Point of Acceptance: Project site
Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Corrugated Pipe Culverts and Pipe Arch Culverts

Submittals:

Quality Assurance: Visual Inspection

Assurance Frequency: Each Shipment

Point of Acceptance: Project site

Out of Spec Action: Rejection

Documentation/Report:

Revised: May 2006

02610

Standard Specification

Related Items: N/A

Type of Construction: Smooth-lined Pipe Culverts and Pipe Arch Culverts Excluding

Concrete Pipe

Submittals:

Quality Assurance: Manufacturer's Certificate of Compliance

Assurance Frequency: Each Shipment
Point of Acceptance: Project site
Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Smooth-lined Pipe Culverts and Pipe Arch Culverts Excluding

Concrete Pipe

Submittals:

Quality Assurance: Visual Inspection

Assurance Frequency: Each Shipment

Point of Acceptance: Project site

Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Aluminized Pipe

Submittals:

Quality Assurance: Manufacturer's Certificate of Compliance

Assurance Frequency: Each Shipment
Point of Acceptance: Project site
Out of Spec Action: Rejection

Documentation/Report:

02610

Standard Specification

Related Items: N/A

Type of Construction: Aluminized Pipe

Submittals:

Quality Assurance: Visual Inspection

Assurance Frequency: Each Shipment

Point of Acceptance: Project site

Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Pipe - Concrete

Submittals:

Quality Assurance: Manufacturer's Certificate of Compliance. Attach Quality

Control (QC) test report for each production run or lot of pipe represented. The QC test report must include: Load bearing (D-load), compressive strength, permeability and visual inspection

pass/fail test results for each production run or lot represented

Assurance Frequency: Each Shipment

Point of Acceptance: Project site
Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Pipe - Concrete

Submittals:

Quality Assurance: Visual Inspection
Assurance Frequency: Each Shipment
Point of Acceptance: Project site
Out of Spec Action: Rejection

Documentation/Report:

02610 Standard Specification

Related Items: N/A

Type of Construction: Concrete

Submittals:

Quality Assurance: Per Section 03055 except as follows: Mix design (trial batches)

must be submitted and approved by the Region Lab each new

calendar year.

Assurance Frequency: N/A
Point of Acceptance: N/A
Out of Spec Action: N/A

Documentation/Report:

Type of Construction: Pipe - Metal

Submittals:

Quality Assurance: Test Report

Assurance Frequency: Issued by Central Lab based on tests performed prior to

shipment. A test report will accompany the shipment. All

pretested material will be tagged with an orange UDOT sticker.

Point of Acceptance: Manufacturer's Plant or Central Lab

Out of Spec Action: Rejection

Documentation/Report:

Type of Construction: Pipe - Metal

Submittals:

Quality Assurance: Visual Inspection

Assurance Frequency: Each Shipment

Point of Acceptance: Project site

Out of Spec Action: Rejection

Documentation/Report: