

UDOT Minimum Sampling and Testing Requirement

Revised: May 2006

03575 Flowable Fill

03575 Standard Specification

Related Items: N/A

Type of Construction: Flowable Fill

Submittals:

Quality Assurance: Slump Test AASHTO T-119

Assurance Frequency: At startup and daily

Point of Acceptance: N/A

Out of Spec Action: N/A

Documentation/Report:

Type of Construction:

Submittals:

Quality Assurance: Strength Test AASHTO T-22 and T-23

Assurance Frequency: One per mix design per supplier

Point of Acceptance: N/A

Out of Spec Action: N/A

Documentation/Report:

Type of Construction:

Submittals:

Quality Assurance: Sieve Analysis (Coarse and Fine Aggregate) AASHTO T-11 and T-27

Assurance Frequency: One per stockpile in advance of placement.

Point of Acceptance: N/A

Out of Spec Action: N/A

Documentation/Report:

*Performed or approved by Region Lab **Performed by Contractor and reviewed by Engineer

Printed 6/2/2006